

AI 15617

COMMONWEALTH OF KENTUCKY  
NATURAL RESOURCES & ENVIRONMENTAL PROTECTION CABINET  
DEPARTMENT FOR ENVIRONMENTAL PROTECTION  
DIVISION OF WATER

APPLICATION FOR PERMIT TO CONSTRUCT ACROSS OR ALONG A STREAM  
AND / OR WATER QUALITY CERTIFICATION

Chapter 151 of the Kentucky Revised Statutes requires approval from the Division of Water prior to any construction or other activity in or along a stream that could in any way obstruct flood flows or adversely impact water quality. If the project involves work in a stream, such as bank stabilization, dredging or relocation, you will also need to obtain a 401 Water Quality Certification (WQC) from the Division of Water. This completed form will be forwarded to the Water Quality Branch for WQC processing. The project may not start until all necessary approvals are received from the KDOW. For questions concerning the WQC process, contact the WQC section at 502/564-3410.

If the project will disturb more than 1 acre of soil, you will also need to complete the attached Notice of Intent for Storm Water Discharges, and return both forms to the Floodplain management Section of the KDOW. This general permit will require you to create an implement an erosion control plan for the project.

1. OWNER: Opus North Corporation/Mr. Michael McBrayer 19275A  
Give name of person(s), company, governmental unit, or other owner of proposed project.  
MAILING ADDRESS: 600 North Cleveland Avenue, Suite 190, Westerville, OH 43082  
TELEPHONE #: (614)508-3612 EMAIL: Mike.McBrayer@opusnorth.com
2. AGENT: Civil & Environmental Consultants, Inc./Daniel J. Godec  
Give name of person(s) submitting application, if other than owner.  
ADDRESS: 4274 Glendale-Milford Road, Cincinnati, OH 45242  
TELEPHONE #: (513) 985-0226 EMAIL: dgodec@cecinc.com
3. ENGINEER: Jim Zentmeyer P.E. NUMBER: 18953  
Contact Division of Water if waiver can be granted.  
TELEPHONE #: (513) 985-0226 EMAIL: jzentmeyer@cecinc.com
4. DESCRIPTION OF CONSTRUCTION: The proposed project involves the design and construction of a class "A" speculative industrial building (proposed Hebron Industrial Park) within an approximate 39-acre undeveloped parcel of land. The project will require the placement of clean fill material in ephemeral and intermittent tributaries to Woolper Creek, two wetlands, and one open water feature. For additional information please see the attached cover letter.
5. COUNTY: Boone NEAREST COMMUNITY: Hebron, Kentucky
6. USGS QUAD NAME: Burlington LATITUDE/LONGITUDE: 39°4'34.4"N; 84°43'22.3"W at the southern most portion of the Site
7. STREAM NAME: Unnamed intermittent and ephemeral tributaries to Woolper Creek  
WATERSHED SIZE (in acres): Approximately 79.6 acres
8. LINEAR FEET OF STREAM IMPACTED: Approximately 2,939 linear feet
9. DIRECTIONS TO SITE: From Interstate 275 West, take Exit #8B, going south on North Bend Road. From North Bend Road, turn right onto Litton Lane. Follow Litton Lane until it dead ends. The eastern boundary of the Site is located approximately 570 feet east of the end of Litton Lane.
10. IS ANY PORTION OF THE REQUESTED PROJECT NOW COMPLETE? ☐ Yes ☒ No If yes, identify the completed portion on the drawings you submit and indicate the date activity was completed. DATE: \_\_\_\_\_
11. ESTIMATED BEGIN CONSTRUCTION DATE: Fall 2009

12. **ESTIMATED END CONSTRUCTION DATE:** Fall 2010
13. **HAS A PERMIT BEEN RECEIVED FROM THE US ARMY, CORPS of ENGINEERS?** ☒ Yes ☐ No If yes, attach a copy of that permit. An Individual Clean Water Act Section 404 Permit was previously obtained from the U.S. Army Corps of Engineers when the Site was under previous ownership. This permit was issued on September 10, 2002 (Permit Number 200101347). A general condition of the permit was completion of construction by June 30, 2005. Due to a change in development plans and work being postponed, a new Individual 404 Permit is required from the USACE. The Individual Clean Water Act Section 404 Permit has been submitted concurrently with the Individual 401 WQC.
14. **THE APPLICANT *MUST* ADDRESS PUBLIC NOTICE:**
  - (a) **PUBLIC NOTICE HAS BEEN GIVEN FOR THIS PROPOSAL BY THE FOLLOWING MEANS:**
    - X Public notice in newspaper having greatest circulation in area (provide newspaper clipping or affidavit)
    - Adjacent property owner(s) affidavits (Contact Division of Water for requirements.)
  - (b)        **I REQUEST WAIVER OF PUBLIC NOTICE BECAUSE:**

Contact Division of Water for requirements.
15. **I HAVE CONTACTED THE FOLLOWING CITY OR COUNTY OFFICIALS CONCERNING THIS PROJECT:**

Mr. Jim Key of the Boone County Building Department was contacted to determine if local permits would be required for construction activities associated with the proposed project. Mr. Smith stated that local building permits would be required for the project when construction begins in addition to planning and zoning approval prior to development.

Give name and title of person(s) contacted and provide copy of any approval city or county may have issued.
16. **LIST OF ATTACHMENTS:** Please see attached cover letter.

List plans, profiles, or other drawings and data submitted. Attach a copy of a 7.5 minute USGS topographic map clearly showing the project location.
17. **I, Michael McBrayer (owner) CERTIFY THAT THE OWNER OWNS OR HAS EASEMENT RIGHTS ON ALL PROPERTY ON WHICH THIS PROJECT WILL BE LOCATED OR ON WHICH RELATED CONSTRUCTION WILL OCCUR** (for dams, this includes the area that would be impounded during the design flood).
18. **REMARKS:** For additional information regarding the proposed project, please see the attached cover letter and attachments.

I hereby request approval for construction across or along a stream as described in this application and any accompanying documents. To the best of my knowledge, all the information provided is true and correct.

**SIGNATURE:**

Owner or Agent sign here. (If signed by Agent, a Power of Attorney must be attached to this application.)

Owner or Agent sign here. (If signed by Agent, a Power of Attorney should be attached.)

DATE: 3-16-04

**SIGNATURE OF LOCAL FLOODPLAIN COORDINATOR:**

**Permit application will be returned to applicant if not properly endorsed by the local floodplain coordinator.**

**DATE:** \_\_\_\_\_

**SUBMIT APPLICATION AND ATTACHMENTS TO:**


**Floodplain Management Section  
Division of Water  
14 Reilly Road  
Frankfort, KY 40601**



**Civil & Environmental  
Consultants, Inc.**

4274 Glendale Milford Road  
Cincinnati, Ohio 45242

Phone: (513) 985-0226 FAX: (513) 985-0228



**LETTER OF TRANSMITTAL**

**TO:** Floodplain Management Section **DATE:** March 19, 2009  
Kentucky Division of Water  
**FROM:** Maggie Vuturo Bosiljevac **CC:**  
**PROJECT:** Hebron Industrial Park **PROJECT No.:** 070-508.0006  
**LOCATION:** Hebron, Boone Co., Kentucky  
**SUBJECT:** Application for Permit to Construct Across or Along a Stream/Individual Clean Water Act Section 401 Water Quality Certification

**DELIVERY:** Courier: ☐ Priority ☒ Standard ☐ Two Day Electronic Mail: ☐

Dear Sir/Madam:

We are sending you the following. If enclosures are not as noted, kindly notify us at once.

COPIES	DESCRIPTION
2	401 Application/Letter
1	Public Notice Affidavit
1	\$2,500 Check for Permit Fee

THESE ARE TRANSMITTED as checked below:

For Approval	<input type="checkbox"/>	Approved as submitted	<input type="checkbox"/>	Resubmit	_____	copies for distribution
For Your Use	<input checked="" type="checkbox"/>	Approved as noted	<input type="checkbox"/>	Submit	_____	copies for distribution
As Requested	<input type="checkbox"/>	Returned for corrections	<input type="checkbox"/>	Return	_____	corrected prints

**REMARKS:** Attached please find two copies of an Application for Permit to Construct Across or Along a Stream/Individual Clean Water Act Section 401 Water Quality Certification for the proposed Hebron Industrial Park located in Hebron, Boone County, Kentucky. Also attached is a copy of the Affidavit of Publication and a \$2,500 check for the permit fee. Please contact me at (513) 985-0226 or via email at [mbosiljevac@cecinc.com](mailto:mbosiljevac@cecinc.com) with any questions regarding the permit application.

**COPY: FILE**

**SIGNED:**

Maggie Vuturo Bosiljevac  
Assistant Project Manager

RECEIVED

MAR 05 2009

# Affidavit of Publication

Publisher's Fee

\$368.00

Affidavit Charge


\$10.00

State of Ohio

}  
}  
} SS.

Hamilton County

}  
}



Personally appeared \_\_\_\_\_ Crystal Williams

Of The Enquirer, a newspaper printed in Cincinnati, Ohio and published in Cincinnati, said County and State, and of general circulation in said county, who being duly sworn depose and saith that the advertisement of which the annexed is a true copy, has been published in said newspaper 3 times, once in each issue as follows.

## PUBLIC NOTICE

Notice is hereby given that Opus North Corporation (600 North Cleveland Avenue, Suite 190, Westerville, Ohio, 43082), will file an application with the Natural Resources and Environmental Protection Cabinet for the industrial development of an approximate 39-acre property located in Hebron, Boone County, Kentucky. The project requires the fill of portions of ten ephemeral and intermittent tributaries to Woolper Creek, two wetlands, and one open water area. The Site is located south of Interstate 275, north of Petersburg Road, and west of Litton Lane. The project is scheduled to commence in fall 2009. Comments or objections concerning this application shall be directed to: Kentucky Division of Water, Water Resources Branch, 14 Reilly Road, Frankfort Office Park, Frankfort, Kentucky 40601. Phone: (502) 564-3410. 1001443688

2/23/09

2/24/09

2/25/09

X Cincinnati Enquirer

Kentucky Enquirer

X Cincinnati.Com

*Crystal Williams*  
Crystal Williams

AFFIANT

Sworn to before me this

2/27/09


*Doris Thomas*  
Notary Public of Ohio



Doris Thomas  
Notary Public, State of Ohio  
My Commission Expires 02-21-2012

February 19, 2009

Floodplain Management Section  
Kentucky Division of Water  
14 Reilly Road  
Frankfort, KY 40601



To Whom It May Concern:

Subject: Application for Permit to Construct Across or Along a Stream and Individual Clean Water Act Section 401 Water Quality Certification  
Proposed Hebron Industrial Park  
Opus North Corporation  
Hebron, Boone County, Kentucky  
CEC Project No. 070-508.0006

On behalf of Opus North Corporation (Opus), Civil & Environmental Consultants, Inc. (CEC) hereby requests Individual Clean Water Act Section 401 Water Quality Certification (WQC) and Permit to Construct Across or Along a Stream authorization for the placement of fill within ephemeral streams, intermittent streams, open water areas, and wetlands within the proposed Hebron Industrial Park (the Site). Because impacts to waterbodies exceed allowable impacts under Nationwide Permit (NWP) 39 – Commercial and Institutional Developments, an Individual Section 404 Water Quality Certification will be obtained from the U.S. Army Corps of Engineers (USACE) – Louisville District. Waterbody impacts also exceed the limits set forth by the Kentucky Division of Water (KDOW) General Certification for NWP 39, therefore an Individual Section 401 WQC/Application for Permit to Construct Across or Along a Stream from KDOW is required for the Site. The permit application is included as Attachment A. A jurisdictional waters delineation of the Site was conducted by CEC on March 4, 2008, March 17, 2008, and April 2, 2008. A copy of the jurisdictional waters delineation report is included as Attachment B.

### Civil & Environmental Consultants, Inc.

**Cincinnati** 4274 Glendale Milford Road  
Cincinnati, Ohio 45242  
Ph: 513/985-0226 / Fx: 513/985-0228  
Toll Free 800/759-5614  
E-mail [cincinnati@cecinc.com](mailto:cincinnati@cecinc.com)  
Corporate Web Site <http://www.cecinc.com>

**Pittsburgh** 800/365-2324  
**Chicago** 887/963-6026  
**Cleveland** 866/507-2324  
**Columbus** 888/598-6808  
**Detroit** 866/380-2324

**Export** 800/899-3610  
**Indianapolis** 877/746-0749  
**Nashville** 800/763-2326  
**Phoenix** 602/953-7705  
**St. Louis** 866/250-3679



Additional permits/clearances required prior to the start of construction include Endangered Species Act clearance from the United State Fish and Wildlife Service (USFWS) Frankfort Ecological Services Field Office and Section 106 of the National Historic Preservation Act clearance from the Kentucky Heritage Council State Historic Preservation Office (SHPO). These clearances were requested in writing on January 14, 2009. Clearance has been received from the USFWS via their response letter dated February 3, 2009; a copy of this letter is included in Appendix C. Upon receipt of the remaining clearances, CEC will send applicable copies of the correspondence to your office.

The Site consists of approximately 39 acres of land located south of Interstate 275 (I-275), north of Petersburg Road, and west of Litton Lane, in Hebron, Boone County, Kentucky. The latitude and longitude coordinates for the southern most portion of the Site are 39°4'34.4"N and 84°43'22.3"W, respectively. The location of the Site is indicated on the attached site location map (Figure 1).

According to the U.S. Geological Survey (USGS) 7.5-minute Burlington, Kentucky quadrangle topographic map (Figure 1), the Site primarily consists of rolling hills. Elevations on the Site range from approximately 835 to 895 feet above mean sea level. Surface water drainage from the Site generally flows east to west toward an unnamed tributary of Woolper Creek which originates within the Site.

Public notice is a requirement for both the Application for Permit to Construct Across or Along a Stream and Section 401 Water Quality Certification. Public notice for the Site has been submitted for publication to The Cincinnati Enquirer by CEC. A copy of the proof of publication will be sent to the KDOW upon receipt.

## **1.0 STREAM IMPACTS**

A jurisdictional waters delineation reconnaissance of the Site identified ten streams within and adjacent to the Site: two interpreted jurisdictional unnamed ephemeral/intermittent tributaries to



Woolper Creek (Streams 3 and 5), six interpreted jurisdictional ephemeral streams that drain within the Site to Stream 3 (Streams 1, 2, 2b, 4, 8, 9) and two interpreted jurisdictional ephemeral streams that drain to Stream 5 outside of the Site boundary (Streams 6 and 7). Upstream portions of Streams 3 and 5 within the Site have been identified as ephemeral. Table 1 outlines the streams located within the Site and the stream impacts that are proposed for development of the Site. Locations of the streams are shown on the attached jurisdictional waters delineation map (Figure 2). For additional information regarding these streams, please see the attached jurisdictional waters delineation report (Attachment B). Photographs of the streams are included in the jurisdictional waters delineation report, with the location and orientation of the photographs indicated on the photograph location map (Figure 5) in the jurisdictional waters delineation report.

<b>TABLE 1</b> <b>STREAM INFORMATION</b> <b>Proposed Hebron Industrial Park</b> <b>Boone County, Kentucky</b>				
Stream Segment Identifier	Approximate On-site Length (linear feet)		Approximate Proposed Impact (linear feet)	
	Ephemeral	Intermittent	Ephemeral	Intermittent
Stream 1	238	NA	238	NA
Stream 2	643	NA	643	NA
Stream 2B	134	NA	134	NA
Stream 3	591	592	591	592
Stream 4	85	NA	85	NA
Stream 5	401	372	401	106
Stream 6	118	NA	0	NA
Stream 7	101	NA	0	NA
Stream 8	63	NA	63	NA
Stream 9	86	NA	86	NA
<b>SUBTOTAL</b>	<b>2,460</b>	<b>964</b>	<b>2,241</b>	<b>698</b>
<b>TOTAL</b>	<b>3,424</b>		<b>2,939</b>	

Notes: NA = Not Applicable



## 2.0 WETLAND IMPACTS

The jurisdictional waters delineation of the Site identified one forested wetland (Wetland 1) and one emergent wetland (Wetland 2) within the Site. Wetland 1 is located within the floodplain of Stream 3. Wetland 2 is located between Pond 1 and Interstate 275. Table 2 outlines the wetland acreage within the Site and the proposed wetland impacts that will occur within the Site. Locations of the wetlands are shown on the attached jurisdictional waters delineation map (Figure 2). For additional information regarding these wetlands, please see the attached jurisdictional waters delineation report (Attachment B). Photographs of the wetlands are included in the jurisdictional waters delineation report, with the location and orientation of the photographs indicated on the photograph location map (Figure 5) in the jurisdictional waters delineation report.

<b>TABLE 2 WETLAND IMPACTS Proposed Hebron Industrial Park Boone County, Kentucky</b>			
<b>Wetland Identifier</b>	<b>Wetland Classification</b>	<b>Approximate Acreage Within Site (Acres)</b>	<b>Approximate Proposed Impact (Acres)</b>
Wetland 1	Forested	0.09	0.09
Wetland 2	Emergent	0.13	0.13
<b>Total</b>	--	<b>0.22</b>	<b>0.22</b>

## 3.0 OPEN WATER IMPACTS

The jurisdictional waters delineation study conducted within the Site identified one open water feature (Pond 1). Pond 1 is adjacent to Wetland 2 within the northern portion of the Site. Water flows east from Wetland 2 to Pond 1, then to Stream 5. Table 3 outlines the open water area acreage within the Site and the proposed impacts that will occur within the Site. The location of the open water area is shown on the attached jurisdictional waters delineation map (Figure 2). For additional information regarding the open water area, please see the attached jurisdictional





waters delineation report (Attachment B). Photographs of the open water area are included in the jurisdictional waters delineation report, with the location and orientation of the photographs indicated on the photograph location map (Figure 5) in the jurisdictional waters delineation report.

<b>TABLE 3 OPEN WATER AREA IMPACTS Proposed Hebron Industrial Park Boone County, Kentucky</b>		
<b>Open Water Area Identifier</b>	<b>Approximate Acreage Within Site (Acres)</b>	<b>Approximate Proposed Impact (Acres)</b>
Pond 1	0.27	0.27
<b>Total</b>	<b>0.27</b>	<b>0.27</b>

#### **4.0 PROPOSED MITIGATION**

Representatives of CEC and Opus met with Mr. Todd Hagman of the Louisville District of the USACE for a pre-application meeting on April 22, 2008, to discuss mitigation requirements for the Site. Opus proposes to mitigate jurisdictional waterbody impacts using a combination of on-site storm water controls and fees in lieu of mitigation. Ephemeral stream impacts will be mitigated through the installation of pavement catch basins, perimeter drainage controls, and storm water controls at the Site. This will include the construction of down spout drains that will drain to a detention basin located in the northwestern portion of the Site. These features are shown on the attached Preliminary Grading Plan (Attachment D).

Opus proposes to mitigate intermittent stream impacts and wetland impacts off-site, through in-lieu-fees. The proposed in-lieu-fees would be payable to the Stream and Wetland Restoration Fund (Stream Fund) administered by the USACE and the KDOW and managed by the Northern Kentucky University (NKU) Center for Applied Ecology.



## 5.0 CONCLUSION

On behalf of Opus, CEC requests authorization for this Application for Permit to Construct Across or Along a Stream and Individual Clean Water Act Section 401 WQC for the placement of clean fill material in waterbodies associated with the development of the proposed Hebron Industrial Park. Individual Clean Water Act Section 401 WQC/Application for Permit to Construct Across or Along a Stream from KDOW is required for the Site based on exceeding the limits of waterbody impacts set forth under the KDOW General Certification of NWP 39.

We appreciate your review of this permit application and thank you for your time and consideration. Please do not hesitate to contact us at (513) 985-0226 if you have questions or need any additional information.

Respectfully submitted,

CIVIL & ENVIRONMENTAL CONSULTANTS, INC.

A handwritten signature in black ink, reading "Daniel J. Godec".

Daniel J. Godec  
Project Manager

A handwritten signature in black ink, reading "James E. Zentmeyer".

James E. Zentmeyer, P. E.  
Principal


Attachments: Figure 1 – Site Location Map  
Figure 2 – Jurisdictional Waters Delineation Map  
Attachment A – Application for Permit to Construct Across or Along a Stream  
and Individual 401 Water Quality Certification  
Attachment B – Jurisdictional Waters Delineation Report  
Attachment C – Agency Clearance Documentation  
Attachment D – Preliminary Grading Plan

cc: Mr. Michael McBrayer, Opus North Corporation  
Mr. Jon Blaha, Opus Corporation

---

# FIGURES

---



SOURCE: USGS 7.5-MINUTE TOPOGRAPHIC QUADRANGLE MAP - BURLINGTON, KENTUCKY, 1984.



**Civil & Environmental Consultants, Inc.**  
Cincinnati, OH

(513) 985-0226 (800) 759-5614

Pittsburgh, PA Chicago, IL Cleveland, OH Columbus, OH Detroit, MI  
Export, PA Indianapolis, IN Nashville, TN St. Louis, MO

DWN. BY: MJB

SCALE:

DATE:

**Site Location Map**

**OPUS NORTH CORPORATION**

Hebron Industrial Park -

Heiman/McGlasson Property

Hebron, Boone County, Kentucky

CHKD. BY: MAVB

1" equals 2,000 feet

05/14/2008



PROJECT NO:

070-508

FIGURE NO:

1

J:\Projects\2007\070508\Maps\401\Figure\_2.mxd - 5/14/2008 @ 8:30:17 AM



- Wetland Determination Test Pit
- Ephemeral Stream
- Intermittent Stream
- Pond Length
- ▭ Pond Feature
- ▨ Wetland Feature
- ▭ Approximate Site Boundary

SOURCE: PORTION OF AN ESRI IMAGE MAP SERVICE - <http://services.arcgisonline.com/v92>, SERVICE NAME - 13\_Imagery\_Prime\_World\_2D



**Civil & Environmental Consultants, Inc.**  
Cincinnati, OH

(513) 985-0226 (800) 759-5614

Pittsburgh, PA Chicago, IL Cleveland, OH Columbus, OH Detroit, MI  
Export, PA Indianapolis, IN Nashville, TN St. Louis, MO

## Jurisdictional Waters Delineation Map OPUS NORTH CORPORATION

Hebron Industrial Park -  
Heiman/McGlasson Property  
Hebron, Boone County, Kentucky

DWN. BY: MJB  
CHKD. BY: MAVB

SCALE:  
1" equals 400'

DATE:  
05/14/2008

PROJECT NO:  
070-508

FIGURE NO:  
2

---

**ATTACHMENT A**

**APPLICATION FOR PERMIT TO CONSTRUCT ACROSS OR ALONG A  
STREAM AND INDIVIDUAL 401 WATER QUALITY CERTIFICATION**

---

**COMMONWEALTH OF KENTUCKY  
NATURAL RESOURCES & ENVIRONMENTAL PROTECTION CABINET  
DEPARTMENT FOR ENVIRONMENTAL PROTECTION  
DIVISION OF WATER**

**APPLICATION FOR PERMIT TO CONSTRUCT ACROSS OR ALONG A STREAM  
AND / OR WATER QUALITY CERTIFICATION**

Chapter 151 of the Kentucky Revised Statutes requires approval from the Division of Water prior to any construction or other activity in or along a stream that could in any way obstruct flood flows or adversely impact water quality. If the project involves work in a stream, such as bank stabilization, dredging or relocation, you will also need to obtain a 401 Water Quality Certification (WQC) from the Division of Water. This completed form will be forwarded to the Water Quality Branch for WQC processing. The project may not start until all necessary approvals are received from the KDOW. For questions concerning the WQC process, contact the WQC section at 502/564-3410.

If the project will disturb more than 1 acre of soil, you will also need to complete the attached Notice of Intent for Storm Water Discharges, and return both forms to the Floodplain management Section of the KDOW. This general permit will require you to create an implement an erosion control plan for the project.

1. OWNER: Opus North Corporation/Mr. Michael McBrayer 19275A  
Give name of person(s), company, governmental unit, or other owner of proposed project.  
MAILING ADDRESS: 600 North Cleveland Avenue, Suite 190, Westerville, OH 43082  
TELEPHONE #: (614)508-3612 EMAIL: Mike.McBrayer@opusnorth.com
2. AGENT: Civil & Environmental Consultants, Inc./Daniel J. Godec  
Give name of person(s) submitting application, if other than owner.  
ADDRESS: 4274 Glendale-Milford Road, Cincinnati, OH 45242  
TELEPHONE #: (513) 985-0226 EMAIL: dgodec@cecinc.com
3. ENGINEER: Jim Zentmeyer P.E. NUMBER: 18953  
Contact Division of Water if waiver can be granted.  
TELEPHONE #: (513) 985-0226 EMAIL: jzentmeyer@cecinc.com
4. DESCRIPTION OF CONSTRUCTION: The proposed project involves the design and construction of a class "A" speculative industrial building (proposed Hebron Industrial Park) within an approximate 39-acre undeveloped parcel of land. The project will require the placement of clean fill material in ephemeral and intermittent tributaries to Woolper Creek, two wetlands, and one open water feature. For additional information please see the attached cover letter.
5. COUNTY: Boone NEAREST COMMUNITY: Hebron, Kentucky
6. USGS QUAD NAME: Burlington LATITUDE/LONGITUDE: 39°4'34.4"N; 84°43'22.3"W at the southern most portion of the Site
7. STREAM NAME: Unnamed intermittent and ephemeral tributaries to Woolper Creek  
WATERSHED SIZE (in acres): Approximately 79.6 acres
8. LINEAR FEET OF STREAM IMPACTED: Approximately 2,939 linear feet
9. DIRECTIONS TO SITE: From Interstate 275 West, take Exit #8B, going south on North Bend Road. From North Bend Road, turn right onto Litton Lane. Follow Litton Lane until it dead ends. The eastern boundary of the Site is located approximately 570 feet east of the end of Litton Lane.
10. IS ANY PORTION OF THE REQUESTED PROJECT NOW COMPLETE? ☐ Yes ☒ No If yes, identify the completed portion on the drawings you submit and indicate the date activity was completed. DATE: \_\_\_\_\_
11. ESTIMATED BEGIN CONSTRUCTION DATE: Fall 2009





**COMMONWEALTH OF KENTUCKY  
ENERGY AND ENVIRONMENT CABINET  
DEPARTMENT FOR ENVIRONMENTAL PROTECTION  
DIVISION OF WATER**

**INDIVIDUAL KENTUCKY WATER QUALITY CERTIFICATION  
FEE PAYMENT**

401 KAR 9:020 Section 401 Water Quality Certification Fees and Certification Timetable

KRS 224.16-050 authorizes the cabinet to certify pursuant to 33 U.S.C. 1341 that applicants for a federal permit regarding the construction or operation of facilities, which may result in a discharge of dredged or fill material into the waters of the Commonwealth, as defined in KRS 224.01-010(33), shall comply with the applicable provisions of the Federal Water Pollution Control Act, 33 U.S.C. 1251 et seq. KRS 224.10-100 authorizes the cabinet to establish a fee for the cost of processing applications for permits authorized under KRS Chapter 224. The project may not start until all necessary fees are paid and approvals are received from KDOW. For questions concerning the WQC process, contact the WQC Section at 502-564-3410. For more information: [HTTP://WWW.WATER.KY.GOV/PERMITTING/WQCERT/](http://www.water.ky.gov/permitting/wqcert/)

1. **OWNER:** Opus North Corporation/Mr. Michael McBrayer  
Provide name of person(s), company, governmental unit or other owner of proposed project.  
**MAILING ADDRESS:** 600 North Cleveland Avenue, Suite 190, Westerville, OH 43082  
**TELEPHONE #:** (614)508-3612 **E-MAIL:** Mike.McBrayer@opusnorth.com  
**AGENCY INTEREST (AI) # OF PROJECT:** \_\_\_\_\_ (assigned by KDOW)
2. **AGENT:** Civil & Environmental Consultants, Inc./Daniel J. Godec  
Provide name of person(s) submitting application, if other than owner.  
**ADDRESS:** 4274 Glendale-Milford Road, Cincinnati, OH 45242  
**TELEPHONE #:** (513) 985-0226 **E-MAIL:** dgodec@cecinc.com
3. **BRIEF DESCRIPTION OF CONSTRUCTION:** The proposed project involves the design and construction of a class "A" speculative industrial building (proposed Hebron Industrial Park) within an approximate 39-acre undeveloped parcel of land. The project will require the placement of clean fill material in ephemeral and intermittent tributaries to Woolper Creek, two wetlands, and one open water feature. For additional information please see the attached cover letter
4. **COUNTY:** Boone **NEAREST COMMUNITY:** Hebron, Kentucky
5. **STREAM NAME(S):** Unnamed intermittent and ephemeral tributaries to Woolper Creek  
**LATITUDE/LONGITUDE:** 39°4'34.4"N; 84°43'22.3"W at the southern most portion of the Site (reference attached sheet for tabulated summary of additional coordinates.  
(Start and end points of each individual impact; add more sheets if necessary.)
7. **TOTAL LINEAR FEET OF STREAM IMPACTED:** Approximately 2,939 linear feet  
**WETLAND ACRES IMPACTED:** Approximately 0.22 acres
8. **EXEMPTED FROM FEE BECAUSE:**  
(A) {Personal Residence: \_\_\_\_\_} (B) Agricultural Operation: \_\_\_\_\_
9. **FEES:**  
Stream impact greater than 500 linear feet and less than 1,000 linear feet: Fee - \$1,000.00 \_\_\_\_\_  
Stream impact 1,000 linear feet to 5,000 linear feet: Fee - \$2,500.00 X \_\_\_\_\_  
Stream impact greater than 5,000 linear feet: Fee - \$5,000.00 \_\_\_\_\_  
Wetland impacts: Fee \$500.00 per acre not to exceed \$5,000.00 \_\_\_\_\_  
Total Fee Paid: \$2,500.00

To the best of my knowledge, all the information provided is true and correct.

**SIGNATURE:** \_\_\_\_\_

Owner or Agent sign here. (If signed by Agent, attach Power of Attorney.)

**DATE:** 3-16-09

**Make check to: KY STATE TREASURER**

**MAIL TO:**

**Kentucky Division of Water  
Water Quality Certification Section  
200 Fair Oaks Lane  
Frankfort, KY 40601**

**Proposed Hebron Industrial Park**  
**Litton Lane, Hebron, Boone County, Kentucky**  
**Opus North Corporation**

**Summary of Stream Impact Coordinates**  
**for**  
**Individual Kentucky Water Quality Certification Fee Payment**

<b>MAP_LABEL</b>	<b>POSITION</b>	<b>Longitude (DD)</b>	<b>Latitude (DD)</b>	<b>Longitude (DMS)</b>	<b>Latitude (DMS)</b>
Pond	Begin	-84.723891	39.080277	-84 43 26	39 04 48
Pond	End	-84.724399	39.080309	-84 43 27	39 04 49
Stream 1	Begin	-84.723038	39.077564	-84 43 22	39 04 39
Stream 1	End	-84.722795	39.078163	-84 43 22	39 04 41
Stream 2	Begin	-84.722076	39.077501	-84 43 19	39 04 39
Stream 2	End	-84.723380	39.078838	-84 43 24	39 04 43
Stream 2b	Begin	-84.722314	39.077287	-84 43 20	39 04 38
Stream 2b	End	-84.722230	39.077628	-84 43 20	39 04 39
Stream 3 - eph	Begin	-84.721269	39.078706	-84 43 16	39 04 43
Stream 3 - Int	Begin	-84.723077	39.078835	-84 43 23	39 04 43
Stream 3 - Int	End	-84.725221	39.079251	-84 43 30	39 04 45
Stream 3 - eph	End	-84.723077	39.078835	-84 43 23	39 04 43
Stream 4	Begin	-84.725037	39.079007	-84 43 30	39 04 44
Stream 4	End	-84.725080	39.079204	-84 43 30	39 04 45
Stream 5 - eph	Begin	-84.724280	39.080439	-84 43 27	39 04 49
Stream 5 - eph	End	-84.724961	39.080105	-84 43 29	39 04 48
Stream 5 - Int	Begin	-84.724961	39.080105	-84 43 29	39 04 48
Stream 5 - Int	End	-84.725292	39.080086	-84 43 31	39 04 48
Stream 8	Begin	-84.722243	39.079048	-84 43 20	39 04 44
Stream 8	End	-84.722351	39.078906	-84 43 20	39 04 44
Wetland 1	Begin	-84.722563	39.078898	-84 43 21	39 04 44
Wetland 1	End	-84.723077	39.078829	-84 43 23	39 04 43
Wetland 2	Begin	-84.723439	39.080569	-84 43 24	39 04 50
Wetland 2	End	-84.723922	39.080316	-84 43 26	39 04 49

---

**ATTACHMENT B**

**JURISDICTIONAL WATERS DELINEATION REPORT**

---



# JURISDICTIONAL WATERS DELINEATION REPORT

OPUS NORTH CORPORATION  
38.8-ACRE HEIMAN/MCGLASSON PROPERTY  
HEBRON, BOONE COUNTY, KENTUCKY

Prepared for:

OPUS NORTH CORPORATION

Prepared by:

CIVIL & ENVIRONMENTAL CONSULTANTS, INC.  
CINCINNATI, OHIO

CEC Project No. 070-508.0002

April 18, 2008



## TABLE OF CONTENTS

	<u>Page</u>
1.0 INTRODUCTION .....	1
1.1 General Information.....	1
1.2 Methodology .....	1
2.0 FINDINGS .....	3
2.1 National Wetlands Inventory Map.....	3
2.2 Soils .....	3
2.3 Plant Communities.....	4
2.4 Hydrology .....	5
2.5 Wetlands .....	7
3.0 REGULATORY CONSIDERATIONS.....	9
3.1 Meetings with Regulatory Agencies.....	9
3.2 Regulatory Issues.....	9
4.0 CONCLUSIONS.....	11
5.0 LEVEL OF CARE .....	12
6.0 REFERENCES .....	13

## LIST OF FIGURES

	<u>Figure</u>
Site Location Map.....	1
U.S.D.A. Soils Map .....	2
National Wetlands Inventory Map.....	3
Jurisdictional Waters Delineation Map.....	4
Photograph Location Map.....	5

## LIST OF APPENDICES

	<u>Appendix</u>
Wetland Determination Data Forms .....	I
Site Photographs .....	II



## 1.0 INTRODUCTION

### 1.1 GENERAL INFORMATION

This report presents the findings of a wetland and stream delineation conducted at the 38.8-Acre Heiman/ McGlasson Property (the Property), located in Hebron, Boone County, Kentucky (see Figure 1). The Property is composed of two irregularly-shaped adjacent parcels of land located near the western end of Litton Lane, south of and adjacent to I-275. The Property consists of old field, early successional forest, and second growth forest habitats.

The wetland and stream delineation site visit was conducted by Civil & Environmental Consultants, Inc. (CEC) on March 4, 2008, March 17, 2008, and April 2, 2008.

### 1.2 METHODOLOGY

The purpose of the study was to identify and delineate the boundaries of wetlands and other jurisdictional waters within the proposed project area. The delineation was based on CEC's professional judgment and interpretation of the technical criteria presented in the 1987 *U.S. Army Corps of Engineers Wetlands Delineation Manual* (USACE 1987).

The wetland delineation was conducted using the routine on-site determination method described in the 1987 Corps Manual, supplemented by the *National List of Plant Species That Occur in Wetlands: Northeast Region (Region 1)* (Reed 1988) and *Hydric Soils of the United States* (USDA 1991). Additionally, in areas where disturbance had occurred, CEC made assumptions based upon historic information contained in the soil survey and observed current site conditions. CEC completed the following scope of services to identify and delineate jurisdictional wetland boundaries at the site:


1. Office Data Review: CEC personnel reviewed the U.S. Geological Survey (USGS) topographic map (Figure 1), U.S. Department of Agriculture (USDA) *Soil Survey of Boone, Campbell, and Kenton Counties, Kentucky* (USDA 1989, Figure 2), U.S. Fish & Wildlife Service (USFWS) National Wetlands Inventory (NWI) Map (Figure 3),



and the USDA Natural Resources Conservation Service (NRCS) list of hydric soils for Boone County, Kentucky (USDA 2007). These resources were used to establish site characteristics that aided in the identification of potential wetland areas.

2. Site Reconnaissance: CEC performed the wetland delineation on March 4, 2008, March 17, 2008, and April 2, 2008. The wetland delineation work was completed using the routine on-site determination method. First, plant communities present on the site were identified. The dominant plant species within each community were identified and an assessment was made on whether or not the plant community was dominated by hydrophytic (wetland) plants. Next, a representative test site was located within the plant community and soils were sampled using a spade shovel to assess the presence of hydric soil indicators. Lastly, the test site was inspected for indicators of wetland hydrology (ponding, soil saturation, etc.) were present. If areas having wetland vegetation, hydric soils, and wetland hydrology were found, a test site was located outside the wetland to delineate where the wetland boundary could be located. Additionally, wetlands (if located on the site) were marked in the field with consecutively numbered surveyor's ribbon flags and subsequently located onto the Burlington, Kentucky quadrangle of the USGS 7.5-minute topographic map using a Trimble GeoXT Global Positioning System (GPS) unit. Other potential jurisdictional waters, such as ephemeral, intermittent or perennial streams located within the Property, were also identified, where applicable.
3. Data Collection: Data forms for the routine on-site determination method were completed for ten representative locations within the Property boundaries (see Figure 4 for locations and Appendix I for the wetland data forms). The data forms were completed to record the vegetation, soils and hydrology at each test site. Photographs of the wetlands, streams, and other representative habitats present on the Property were also taken (Appendix II).
4. Preparation of Wetland and Stream Delineation Report: This wetland and stream delineation report documents CEC's methodology, findings, wetland delineation map, regulatory considerations, and conclusions.





## 2.0 FINDINGS

### 2.1 NATIONAL WETLANDS INVENTORY MAP

NWI maps have been prepared by the USFWS based on high altitude infrared aerial photography and limited ground truthing. Wetlands and deep-water habitats are identified on these maps and classified according to the system developed by Cowardin and co-workers (1979). The NWI map for the Burlington, Kentucky quadrangle identified one wetland, a PUBHh, as being present within the Property boundary (Figure 3). This means, according to the Cowardin classification system, that the wetland is a palustrine wetland (P) with an unconsolidated bottom (UB) that is permanently flooded (H) and has been diked/impounded (h).

### 2.2 SOILS

The *Soil Survey of Boone, Campbell, and Kenton Counties, Kentucky* (USDA 1989) shows three soil mapping units on the Property. The soil mapping units identified at the Property are summarized in Table 1. The soils map is presented as Figure 2.

<b>TABLE 1</b> <b>SOILS INFORMATION</b> <b>Proposed Hebron Industrial Park</b> <b>Boone County, Kentucky</b>		
<b>Soil Mapping Unit Name (Symbol)</b>	<b>Taxonomy</b>	<b>Hydric Soil List Designation</b>
Jessup silt loam, 12 to 20 percent slopes (JeD)	Typic Hapludalfs	Not Hydric
Rossmoyne silt loam, 0 to 6 percent slopes (RsB)	Aquic Fraguidalfs	Not Hydric
Rossmoyne silt loam, 6 to 12 percent slopes (RsC)	Aquic Fragiudalfs	Not Hydric

None of the three soil units identified in the study area are listed as hydric by the NRCS (USDA 2007).



## 2.3 PLANT COMMUNITIES

The Property consists of second growth forest, early successional forest, old fields, and an open water/ pond. The second growth forest was in the northwestern portion of the Property, the early successional forest in the eastern portion, the old fields in the central and southern portions, and the pond is present in the north-central portion of the Property. The vegetation found in each wetland sample point has been detailed in the individual wetland determination data forms presented in Appendix I. Representative photos of each habitat type identified on the Property are presented in Appendix II.

The overstory of the second growth forest within the Property was dominated by sugar maple (*Acer saccharum*), white ash (*Fraxinus americana*), common hackberry (*Celtis occidentalis*), box elder (*Acer negundo*), American sycamore (*Platanus occidentalis*), and black cherry (*Prunus serotina*). The understory of this area was dominated by white snake root (*Eupatorium rugosum*), garlic mustard (*Alliaria petiolata*), Amur honeysuckle (*Lonicera maackii*), ground ivy (*Glechoma hederacea*), multiflora rose (*Rosa multiflora*), Japanese honeysuckle (*Lonicera japonica*), and white avens (*Geum canadense*). The overstory of the early successional forest was predominantly white ash, common hackberry, and box elder, although the other species were present as well. The understory was similar to that of the second growth forest. In general, the understory of the second growth and early successional forests was variable but included areas with large patches of Amur honeysuckle.

The overstory of old field habitats, including scattered portions of early successional forest, was dominated by smooth sumac (*Rhus glabra*), common hackberry, box elder, and white ash. The understory of the old field areas was dominated by Allegheny blackberry (*Rubus allegheniensis*), multiflora rose, garlic mustard, Japanese honeysuckle, and various species of goldenrod (*Solidago* spp.) and grasses.

## 2.4 HYDROLOGY

Using CEC's professional judgment and field indicators such as flow, substrate composition, embeddedness, defined bed and banks, and vegetation, CEC identified the following streams within the Project area: an unnamed ephemeral/intermittent tributary of Woolper Creek, three unnamed ephemeral tributaries of Stream 3 (Stream 2, Stream 4, and Stream 8), one unnamed ephemeral/intermittent tributary of Stream 3 (Stream 5), two unnamed ephemeral tributaries of Stream 2 (Stream 1 and Stream 2B), and two unnamed ephemeral tributaries of Stream 5 (Stream 6 and Stream 7). The limits of the streams were recorded in the field with a Trimble GeoXT GPS unit, and subsequently transferred to Figure 4. The on-site lengths are summarized below.

The Property primarily consists of rolling hills. Ground surface elevations on the Property are mapped to range from approximately 835 to 895 feet above mean sea level. As seen in Figure 4, hydrologic features on the Property include eight unnamed ephemeral streams (Streams 1, 2, 2B, 4, 6, 7, 8, and 9) and two unnamed ephemeral/intermittent streams (Stream 3 and Stream 5; Figure 4). Drainage on the Property is generally east to west. Based on CEC's observations, the ephemeral streams appear to be primarily providing conveyance of storm water during and immediately after precipitation events.

<b>TABLE 2 STREAM INFORMATION Proposed Hebron Industrial Park Boone County, Kentucky</b>		
<b>Stream Segment Identifier</b>	<b>Approximate On-site Length (linear feet)</b>	
	<b>Ephemeral</b>	<b>Intermittent</b>
Stream 1	238	NA <sup>1</sup>
Stream 2	643	NA
Stream 2B	134	NA
Stream 3	591	592
Stream 4	85	NA
Stream 5	401	372
Stream 6	118	NA
Stream 7	101	NA
Stream 8	63	NA
Stream 9	86	NA
<b>TOTAL</b>	<b>2,460</b>	<b>964</b>

<sup>1</sup> Not Applicable



A summary of the streams observed on the Property is presented below:

- Stream 1 originates on the Property and flows north into Stream 2 on the Property. Stream 1 is approximately 1 foot wide and primarily contains silt substrates.
- Stream 2 originates east of the Property. This stream flows across the eastern portion of Property and drains into Stream 3 in the center of the Property. Stream 2 varies in width from approximately 1 to 3 feet wide and primarily contains silt substrates.
- Stream 2B originates in the southwestern portion of the Property and drains northwest into Stream 2 in the Property. Stream 2B is approximately 1 foot wide and primarily contains silt substrates.
- Stream 3 originates in the eastern portion of the Property, drains through the center of the Property and exits the Property to the west. Stream 3 varies from approximately 3 feet wide in the eastern portion of the Property to 10 feet wide on the western edge of the Property, and contains a mixture of silt, muck, gravel, sand, and woody debris as substrates.
- Stream 4 originates west of the Property and drains north into Stream 3 within the Property. Stream 4 is approximately 2 feet in width and primarily contains silt substrates.
- Stream 5 originates at Pond 1 and drains west out of the Property and into Stream 3. Stream 5 varies in width from about 1 foot wide at Pond 1 to 5 feet wide at the western edge of the Property, and contains a mixture of silt, sand, gravel, muck, woody debris, and cobble substrates.
- Stream 6 originates within the Property and drains south into Stream 5 within the Property. Stream 6 is approximately 1 foot in width and primarily contains silt, muck and woody debris as substrates.
- Stream 7 originates from roadside drainage of Interstate Route 275 north of the Property and drains southwest through the Property and into Stream 3. Stream 7 is approximately 4 feet in width and primarily contains sand, silt, and muck substrates.
- Stream 8 originates in the eastern portion of the Property and drains south into Stream 3 within the Property. Stream 8 varies from approximately 1 to 2 feet in width and primarily contains silt and muck substrates.
- Stream 9 originates within the northeastern portions of the Property and drains into Stream 3 just east of the eastern boundary of the Property. Stream 9 averages approximately 3 feet wide and contains silt substrates.

One open water area (Pond 1), comprising 0.27 acre, was identified on the Property. The open water area is directly adjacent to Wetland 2. Drainage of the open water area is by means of Stream 5.



TABLE 3 OPEN WATER AREA INFORMATION Proposed Hebron Industrial Park Boone County, Kentucky	
Open Water Area Identifier	On-site Area (acres)
Pond 1	0.27
TOTAL	0.27

## 2.5 Wetlands

During the site visits, CEC sampled wetland determination test pits using the on-site wetland determination method described above in Section 1.2. CEC focused on areas shown as having areas with vegetation that appeared to be potentially hydrophytic, and/or on areas shown on the NWI maps as being within a wetland.

Ten sites within the Property were sampled using the on-site wetland determination method. The wetland determination data forms for these 10 sites are provided in Appendix I, and representative photos of the wetland determination sample sites are provided in Appendix II. The location of these wetland determination test sites were recorded using a Trimble GeoXT GPS unit. The locations of sites sampled using the on-site wetland determination method are shown on Figure 4. The photograph locations are shown on Figure 5.

Field investigations resulted in the identification of two interpreted wetlands present within the Property (Wetlands 1 and 2) as summarized below and in Table 4:

- Wetland 1 consists of a palustrine forested wetland located on the floodplain of Stream 3. The wetland comprises approximately 0.09 acre (Figure 4). The overstory of this wetland is dominated by American sycamore, red maple (*Acer rubrum*), box elder, green ash (*Fraxinus pennsylvanica*), and red elm (*Ulmus rubra*). The understory of this wetland is dominated by garlic mustard and multiflora rose.
- Wetland 2 consists of a palustrine emergent wetland located between Pond 1 and Interstate 275. The wetland comprises approximately 0.13 acre. This wetland is dominated by rice cut-grass (*Leersia oryzoides*), green bulrush (*Scirpus atrovirens*), boneset (*Eupatorium perfoliatum*), creeping jenny (*Lysimachia nummularia*) and multiflora rose (*Rosa multiflora*).



**TABLE 4**  
**WETLAND IMPACTS**  
**Proposed Hebron Industrial Park**  
**Boone County, Kentucky**

<b>Open Water Area Identifier</b>	<b>Wetland Classification</b>	<b>Acreage Within Construction Easement</b>
Wetland 1	Palustrine Forested	0.09
Wetland 2	Palustrine Emergent	0.13
<b>TOTAL</b>	--	0.22



### **3.0 REGULATORY CONSIDERATIONS**

#### **3.1 MEETINGS WITH REGULATORY AGENCIES**

No meetings between regulatory agencies and CEC have taken place at the time this report was prepared. The jurisdictional waters delineation findings presented in this document were developed based upon CEC's professional training and experience, and the results of the March 4 and April 12, 2008, site visit.

#### **3.2 REGULATORY ISSUES**

Impacts to jurisdictional streams and wetlands are regulated in the state of Kentucky by the U. S. Army Corps of Engineers (USACE) and the Kentucky Division of Water (KDOW). Discharges of dredged or fill material into waters of the United States, as well as relocation of waters of the United States, require permits from the USACE under the provisions of Section 404 of the Clean Water Act, as well as Section 401 Water Quality Certification from the KDOW.

Based on the results of the jurisdictional waters delineation, CEC identified approximately 3,424 linear feet of interpreted jurisdictional streams on the property. It is noted that this stream length is "all inclusive" and may include significant portions of streams that may not be impacted as part of Opus' proposed construction.

A formal Jurisdictional Determination from the USACE and KDOW is required to verify CEC's wetland delineation findings, prior to initiation of permit issuance. The jurisdictional determination may require a site visit by these agencies.

Two types of Section 404 Clean Water Act permits are available from the USACE to those seeking to develop property. The first type is a Nationwide Permit, which generally covers impacts to less than 200 linear feet of perennial or intermittent streams, less than 300 linear feet of ephemeral streams, or less than 0.5 acre of combined wetland and stream impacts. A pre-construction notification would be required for a Nationwide Permit. If impacts to streams and



wetlands exceed these linear foot and/or acreage limitations, then an Individual Section 404 Permit would likely be required from the USACE and Section 401 Water Quality Certification would be required from the KDOW.

Individual Permits and Section 401 Water Quality Certification require a sequencing review. Sequencing requires the permit applicant to demonstrate that the project purpose cannot be accomplished without impacting wetlands and other jurisdictional waters. If this can be demonstrated, then the applicant is required to further demonstrate that the scope of the project has been revised to minimize impacts to jurisdictional waters. The sequencing process requires that an alternatives analysis be performed, and that the alternatives analysis must address other potential sites. Alternative site plans which attempt to avoid or minimize jurisdictional water impacts must be developed and evaluated. The regulatory agencies will only consider mitigation of jurisdictional water impacts after satisfactory completion of the sequencing requirements. A mitigation plan will be required for unavoidable impacts to jurisdictional streams, open waters, and wetlands.





#### **4.0 CONCLUSIONS**

Ten interpreted jurisdictional streams, one pond comprising 0.27 acre, and two interpreted jurisdictional wetlands comprising 0.22 acre were identified and delineated by CEC within the Property during the site visit. The interpreted jurisdictional streams include two ephemeral/intermittent streams totaling approximately 1,956 linear feet (992 ephemeral linear feet and 964 intermittent linear feet) and eight ephemeral streams totaling approximately 2,270 linear feet. Locations of potentially jurisdictional streams and wetlands were recorded by CEC using a Trimble GeoXT GPS unit. The locations of the interpreted jurisdictional streams, wetlands, and pond are presented in Figure 4. Based on CEC's observations, the ephemeral streams appear to be primarily providing conveyance of storm water during and immediately after precipitation events.



## 5.0 LEVEL OF CARE

The jurisdictional waters delineation services performed by CEC were conducted in a manner consistent with the criteria contained in the 1987 Corps Manual and with the level of care and skill ordinarily exercised by members of the environmental consulting profession practicing contemporaneously under similar conditions in the locality of the project. It must be recognized that the jurisdictional waters delineation was based on field observations and CEC's professional interpretation of the criteria in the 1987 Corps Manual at the time of our fieldwork. Jurisdictional waters determinations may change subsequent to CEC's delineation based on changes in the regulatory criteria, seasonal variations in hydrology, alterations to drainage patterns and other human activities and/or land disturbances. Therefore, the findings and opinions are relevant to the dates of our site activities and should not be relied on to represent conditions at substantially later dates. References herein to interpreted jurisdictional waters on the subject property are the opinion of CEC and are subject to change pending formal review by the USACE and/or KDOW. The actual regulated extent and limits of jurisdictional waters are not established until formally sanctioned by the USACE and KDOW as part of a Jurisdictional Determination.

This report is intended for the use of Opus North Corporation only, consistent with the qualifications outlined herein and the terms and conditions of CEC's proposal. Our services have been performed under mutually agreed upon terms and conditions. If other parties wish to rely on this report, please have them contact us so that a mutual understanding and agreement of the terms and conditions for our services can be established prior to their use of this information.


## 6.0 REFERENCES

- Cowardin, L. M., V. Carter, and F. C. Golet. 1979. Classification of Wetlands and Deep Water Habitats of the United States. U.S. Department of the Interior, Fish and Wildlife Service. Washington D. C. FWS/OBS-79/31.
- U.S. Army Corps of Engineers (USACE), Environmental Laboratory. 1987. Corps of Engineers Wetlands Delineation Manual, Technical Report Y-87-1, U.S. Army Engineer Waterway Experiment Station, Vicksburg, Mississippi.
- Reed, Jr., Porter B. 1988. National List of Plant Species that Occur in Wetlands: Northeast (Region 1). Biological Report 88 (26.1). U.S. Fish and Wildlife Service, Washington, D.C.
- United States Department of Agriculture Soil Conservation Service (USDA). 1991. Hydric Soils of the United States. In cooperation with the National Technical Committee for Hydric Soils. Soil Conservation Service, Washington, D.C.
- United States Department of Agriculture Soil Conservation Service (USDA). 1989. Soil Survey of Boone, Campbell, and Kenton Counties, Kentucky. Soil Conservation Service, Washington, D.C. 67pp + maps.
- United States Department of Agriculture Natural Resources Conservation Service (USDA). 2007. Soil Data Mart: Kentucky Counties.  
<http://soildatamart.nrcs.usda.gov/County.aspx?State=KY>  
Accessed March 5, 2008.


---

## FIGURES

---



1,000 0 1,000 2,000  
Feet



SOURCE: USGS 7.5-MINUTE TOPOGRAPHIC QUADRANGLE MAP - BURLINGTON, KENTUCKY, 1984.



**Civil & Environmental Consultants, Inc.**  
Cincinnati, OH

(513) 985-0226 (800) 759-5614

Pittsburgh, PA Chicago, IL Cleveland, OH Columbus, OH Detroit, MI  
Export, PA Indianapolis, IN Nashville, TN St. Louis, MO

### Site Location Map

**OPUS NORTH CORPORATION**

Hebron Industrial Park -

Heiman/McGlasson Property

Hebron, Boone County, Kentucky

DWN. BY: MJB

SCALE:

DATE:

PROJECT NO:

FIGURE NO:

CHKD. BY: MAVB

1" equals 2,000 feet

03/05/2008

070-508

1

J:\Projects\2007\070508 Maps\WD\Figure\_2.mxd - 3/20/2008 @ 8:32:00 AM



300 0 300 600  
Feet



Soil Features  
Approximate Site Boundary

SOURCE: SOILS DATA OBTAINED FROM THE USDA NCRS WEBSITE (<http://soildatamart.nrcs.usda.gov/>), DATE:  
PORTION OF AN ESRI IMAGE MAP SERVICE - <http://services.arcgisonline.com/v92>, SERVICE NAME - I3 Imagery Prime World 2D



**Civil & Environmental Consultants, Inc.**  
Cincinnati, OH

(513) 985-0226 (800) 759-5614

Pittsburgh, PA Chicago, IL Cleveland, OH Columbus, OH Detroit, MI  
Export, PA Indianapolis, IN Nashville, TN St. Louis, MO

**U.S.D.A. Soils Map**  
**OPUS NORTH CORPORATION**  
Hebron Industrial Park -  
Heiman/McGlasson Property  
Hebron, Boone County, Kentucky

DWN. BY: MJB

SCALE:

DATE:

PROJECT NO:

FIGURE NO:


CHKD. BY: MAVB

1" equals 600'

03/05/2008

070-508

2



SOURCE: NWI MAPPING INFORMATION OBTAINED FROM THE USFWS WEBSITE, 2007. ([http://wetlandswms.er.usgs.gov/imf/imf.jsp?site=extract\\_tool](http://wetlandswms.er.usgs.gov/imf/imf.jsp?site=extract_tool)), .  
 PORTION OF AN ESRI IMAGE MAP SERVICE - <http://services.arcgisonline.com/v92>, SERVICE NAME - I3 Imagery Prime World 2D



**Civil & Environmental Consultants, Inc.**  
 Cincinnati, OH  
 (513) 985-0226 (800) 759-5614

Pittsburgh, PA   Chicago, IL   Cleveland, OH   Columbus, OH   Detroit, MI  
 Export, PA   Indianapolis, IN   Nashville, TN   St. Louis, MO

**National Wetlands Inventory Map**  
**OPUS NORTH CORPORATION**  
 Hebron Industrial Park -  
 Heiman/McGlasson Property  
 Hebron, Boone County, Kentucky

DWN. BY: MJB  
 CHKD. BY: MAVB



SCALE:  
 1" equals 600'

DATE:  
 03/05/2008

PROJECT NO:  
 070-508

FIGURE NO:  
 3

J:\Projects\2007\070508\Maps\WD\WD\_Figure 4.mxd - 4/8/2008 @ 3:55:45 PM



SOURCE: PORTION OF AN ESRI IMAGE MAP SERVICE - <http://services.arcgisonline.com/v92>, SERVICE NAME - I3 Imagery\_Prime\_World\_2D



**Civil & Environmental Consultants, Inc.**  
Cincinnati, OH

(513) 985-0226 (800) 759-5614

Pittsburgh, PA Chicago, IL Cleveland, OH Columbus, OH Detroit, MI  
Export, PA Indianapolis, IN Nashville, TN St. Louis, MO

## Jurisdictional Waters Delineation Map OPUS NORTH CORPORATION

Hebron Industrial Park -  
Heiman/McGlasson Property  
Hebron, Boone County, Kentucky

DWN. BY: MJB  
CHKD. BY: MAVB

SCALE:  
1" equals 400'

DATE:  
03/05/2008



PROJECT NO:  
070-508

FIGURE NO:  
4





NORTH



① Photo Location

□ Approximate Site Boundary

SOURCE: PORTION OF AN ESRI IMAGE MAP SERVICE - <http://services.arcgisonline.com/v92>, SERVICE NAME - I3\_Imagery\_Prime\_World\_2D - CINCINNATI2003.



**Civil & Environmental Consultants, Inc.**  
Cincinnati, OH

(513) 985-0226 (800) 759-5614

Pittsburgh, PA Chicago, IL Cleveland, OH Columbus, OH Detroit, MI  
Export, PA Indianapolis, IN Nashville, TN St. Louis, MO

**Photograph Location Map**  
**OPUS NORTH CORPORATION**  
Hebron Industrial Park -  
Heiman/McGlasson Property  
Hebron, Boone County, Kentucky

DWN. BY: MJB

SCALE:

DATE:

PROJECT NO:

FIGURE NO:

CHKD. BY: MAVB

1" equals 350'

03/05/2008

070-508

5

---

## **APPENDIX I**

# **WETLAND DETERMINATION DATA FORMS**

---

**DATA FORM**  
**ROUTINE WETLAND DETERMINATION**  
**(1987 COE Wetland Delineation Manual)**

<b>Project/Site:</b> 070-508 Litton Lane Property, Hebron, KY <b>Applicant/Owner:</b> Opus North Corporation <b>Investigator(s):</b> Matt Lauffer, Lindsey Hesch	<b>Date:</b> March 4, 2008 <b>County:</b> Boone <b>State:</b> KY
Do normal circumstances exist on the site? Yes <u>  X  </u> No <u>      </u> Is the site significantly disturbed (Atypical?) Yes <u>      </u> No <u>  X  </u> Is the area a potential problem area? Yes <u>      </u> No <u>  X  </u> (if needed, explain on reverse.)	<b>Community ID:</b> old field <b>Plot ID:</b> TP-1

**VEGETATION**

Dominant Plant Species:	Stratum:	Indicator:	Dominant Plant Species:	Stratum:	Indicator:
1. <i>Lonicera maackii</i>	Shrub	UPL	10.		
2. <i>Robinia pseudoacacia</i>	Tree	FACU-	11.		
3.			12.		
4.			13.		
5.			14.		
6.			15.		
7.			16.		
8.			17.		
9.			18.		

Percent of dominant species that are OBL, FACW or FAC (and excluding FAC-) = 0%

**Remarks:**

**HYDROLOGY**

_____ Recorded Data (Describe in Remarks) _____ Stream, Lake, or Tide Gauge <u>  X  </u> _____ Aerial Photographs _____ No Recorded Data Available	<b>Wetland Hydrology Indicators:</b> <b>Primary Indicators:</b> _____ Inundated <u>  x  </u> _____ Saturated in upper 12 inches _____ Water Marks _____ Drift Lines _____ Sediment Deposits _____ Drainage Patterns in Wetlands
<b>Field Observations:</b>  Depth of Surface Water: <u>      0      </u> (inches)  Depth to Free Water in Pit: <u>      8      </u> (inches)  Depth to Saturated Soil: <u>      8      </u> (inches)	<b>Secondary Indicators:</b> _____ Oxidized Root Channels in Upper 12 Inches _____ Water Stained Leaves _____ Local Soil Survey Data _____ FAC-Neutral Test _____ Others (Explain in Remarks)
<b>Remarks:</b>  recent heavy rain and snowmelt	

Project/Site: 070-508 / Opus Litton Lane Property, Hebron, KY  
Site/Area ID: TP-1

## SOILS

<b>Map Unit Name:</b> (Series and Phase): <u>Rossmoyne silt loam, 0 to 6% slopes (RsB)</u> Drainage Class: <u>moderately well drained</u> (Taxonomy Subgroup): <u>Aquic Fraguidalfs</u> Field Observations Confirm Mapped Type? Yes <u>X</u> No <u>      </u>					
<b>Profile Description:</b>					
Depth (inches):	Horizon:	Matrix Color (Munsell Moist):	Mottle Colors (Munsell Moist):	Mottle (Abundance/Size):	Texture, Concretions, Structure:
0-6	A	10YR3/3	NA	NA	loam
6-16	B	10YR4/4	NA	NA	clay loam
<b>Hydric Soil Indicators:</b>					
<u>      </u> Histosol			<u>      </u> Concretions		
<u>      </u> Histic Epipedon			<u>      </u> High Organic Content in Surface Layer in Sandy Soils		
<u>      </u> Sulfidic Odor			<u>      </u> Organic Streaking in Sandy Soil		
<u>      </u> Aquic Moisture Regimes			<u>      </u> Listed on Local Hydric Soils List		
<u>      </u> Reducing Conditions			<u>      </u> Listed on National Hydric Soils List		
<u>      </u> Gleyed or Low Chroma Colors			<u>      </u> Other (Explain in Remarks)		
<b>Remarks:</b>					

## WETLAND DETERMINATION

Hydrophytic Vegetation Present?	Yes <u>      </u>	No <u>X</u>	Is this Sampling Point Within a Wetland? Yes <u>      </u> No <u>X</u>
Wetland Hydrology Present?	Yes <u>X</u>	No <u>      </u>	
Hydric Soils Present?	Yes <u>      </u>	No <u>X</u>	
<b>Remarks:</b>			
recent heavy rain may have caused unusual saturation level of soils			

**DATA FORM**  
**ROUTINE WETLAND DETERMINATION**  
**(1987 COE Wetland Delineation Manual)**

<b>Project/Site:</b> 070-508 Litton Lane Property, Hebron, KY <b>Applicant/Owner:</b> Opus North Corporation <b>Investigator(s):</b> Matt Lauffer, Lindsey Hesch	<b>Date:</b> March 4, 2008 <b>County:</b> Boone <b>State:</b> KY
Do normal circumstances exist on the site? Yes <u>  X  </u> No <u>      </u> Is the site significantly disturbed (Atypical?) Yes <u>      </u> No <u>  X  </u> Is the area a potential problem area? Yes <u>      </u> No <u>  X  </u> (if needed, explain on reverse.)	<b>Community ID:</b> old field <b>Plot ID:</b> TP-2

**VEGETATION**

Dominant Plant Species:	Stratum:	Indicator:	Dominant Plant Species:	Stratum:	Indicator:
1. <i>Rubus allegheniensis</i>	Shrub	FACU-	10.		
2. <i>Solidago canadensis</i>	Herb	FACU	11.		
3. <i>Lonicera japonica</i>	Woody Vine	FAC-	12.		
4. <i>Rhus glabra</i>	Shrub	UPL	13.		
5. <i>Fraxinus americana</i>	Shrub	FACU	14.		
6. <i>Poa</i> sp.	Herb	NI	15.		
7. <i>Rosa multiflora</i>	Shrub	FACU	16.		
8.			17.		
9.			18.		

Percent of dominant species that are OBL, FACW or FAC (and excluding FAC-) = 0%

**Remarks:**

**HYDROLOGY**

<div style="border: 1px solid black; padding: 5px; margin-bottom: 10px;">         Recorded Data (Describe in Remarks)          Stream, Lake, or Tide Gauge  <u>  X  </u> Aerial Photographs          No Recorded Data Available       </div> <div style="border: 1px solid black; padding: 5px;"> <b>Field Observations:</b>           Depth of Surface Water: <u>      0      </u> (inches)           Depth to Free Water in Pit: <u>      10      </u> (inches)           Depth to Saturated Soil: <u>      10      </u> (inches)       </div>	<b>Wetland Hydrology Indicators:</b> Primary Indicators: <u>      </u> Inundated <u>  X  </u> Saturated in upper 12 inches <u>      </u> Water Marks <u>      </u> Drift Lines <u>      </u> Sediment Deposits <u>      </u> Drainage Patterns in Wetlands  Secondary Indicators: <u>      </u> Oxidized Root Channels in Upper 12 Inches <u>      </u> Water Stained Leaves <u>      </u> Local Soil Survey Data <u>      </u> FAC-Neutral Test <u>      </u> Others (Explain in Remarks)
<div style="border: 1px solid black; height: 40px; padding: 5px;"> <b>Remarks:</b>           Recent heavy rain appears to have caused unusually high water table levels       </div>	

Project/Site: 070-508 / Opus Litton Lane Property, Hebron, KY  
 Site/Area ID: TP-2

## SOILS

<b>Map Unit Name:</b>					
(Series and Phase): <u>Rossmoyne silt loam, 6 to 12% slopes (RsC)</u>			Drainage Class: <u>moderately well drained</u>		
(Taxonomy Subgroup): <u>Aquic Fraguidalfs</u>			Field Observations Confirm Mapped Type?		
			Yes <u>X</u> No <u>      </u>		
<b>Profile Description:</b>					
Depth (inches):	Horizon:	Matrix Color (Munsell Moist):	Mottle Colors (Munsell Moist):	Mottle (Abundance/Size):	Texture, Concretions, Structure:
0-10	A	10YR 4/4	NA	NA	loam
10-16	B	10YR 4/6	NA	NA	clay loam
<b>Hydric Soil Indicators:</b>					
<u>      </u> Histosol			<u>      </u> Concretions		
<u>      </u> Histic Epipedon			<u>      </u> High Organic Content in Surface Layer in Sandy Soils		
<u>      </u> Sulfidic Odor			<u>      </u> Organic Streaking in Sandy Soil		
<u>      </u> Aquic Moisture Regimes			<u>      </u> Listed on Local Hydric Soils List		
<u>      </u> Reducing Conditions			<u>      </u> Listed on National Hydric Soils List		
<u>      </u> Gleyed or Low Chroma Colors			<u>      </u> Other (Explain in Remarks)		
<b>Remarks:</b>					

## WETLAND DETERMINATION

Hydrophytic Vegetation Present?	Yes <u>      </u>	No <u>X</u>	Is this Sampling Point Within a Wetland?
Wetland Hydrology Present?	Yes <u>X</u>	No <u>      </u>	
Hydric Soils Present?	Yes <u>      </u>	No <u>X</u>	
<b>Remarks:</b>			
Recent heavy rain appears to have caused unusually high water table levels			

**DATA FORM**  
**ROUTINE WETLAND DETERMINATION**  
**(1987 COE Wetland Delineation Manual)**

<b>Project/Site:</b> 070-508 Litton Lane Property, Hebron, KY <b>Applicant/Owner:</b> Opus North Corporation <b>Investigator(s):</b> Matt Lauffer, Lindsey Hesch	<b>Date:</b> March 4, 2008 <b>County:</b> Boone <b>State:</b> KY
Do normal circumstances exist on the site? Yes <u>  X  </u> No <u>      </u> Is the site significantly disturbed (Atypical?) Yes <u>      </u> No <u>  X  </u> Is the area a potential problem area? Yes <u>      </u> No <u>  X  </u> (if needed, explain on reverse.)	<b>Community ID:</b> forest floodplain <b>Plot ID:</b> TP-3

**VEGETATION**

Dominant Plant Species:	Stratum:	Indicator:	Dominant Plant Species:	Stratum:	Indicator:
1. <i>Fraxinus americana</i>	Tree	FACU	10.		
2. <i>Acer saccharum</i>	Tree	FACU-	11.		
3. <i>Acer negundo</i>	Tree	FAC+	12.		
4. <i>Lonicera maackii</i>	Shrub	UPL	13.		
5. <i>Rosa multiflora</i>	Shrub	FACU	14.		
6. <i>Alliaria petiolata</i>	Herb	FACU-	15.		
7.			16.		
8.			17.		
9.			18.		
Percent of dominant species that are OBL, FACW or FAC (and excluding FAC-) = 17%					
<b>Remarks:</b>					

**HYDROLOGY**

<div style="border-bottom: 1px solid black; margin-bottom: 5px;"> <input type="checkbox"/> Recorded Data (Describe in Remarks)          Stream, Lake, or Tide Gauge       </div> <div style="border-bottom: 1px solid black; margin-bottom: 5px;"> <input checked="" type="checkbox"/> Aerial Photographs       </div> <div style="border-bottom: 1px solid black; margin-bottom: 5px;"> <input type="checkbox"/> No Recorded Data Available       </div>	<b>Wetland Hydrology Indicators:</b> Primary Indicators: <input type="checkbox"/> Inundated <input checked="" type="checkbox"/> Saturated in upper 12 inches <input type="checkbox"/> Water Marks <input type="checkbox"/> Drift Lines <input type="checkbox"/> Sediment Deposits <input type="checkbox"/> Drainage Patterns in Wetlands  Secondary Indicators: <input type="checkbox"/> Oxidized Root Channels in Upper 12 Inches <input type="checkbox"/> Water Stained Leaves <input type="checkbox"/> Local Soil Survey Data <input type="checkbox"/> FAC-Neutral Test <input type="checkbox"/> Others (Explain in Remarks)
<b>Field Observations:</b>  Depth of Surface Water: <u>      0      </u> (inches)  Depth to Free Water in Pit: <u>      0      </u> (inches)  Depth to Saturated Soil: <u>      0      </u> (inches)	
<b>Remarks:</b>	

Project/Site: 070-508 / Opus Litton Lane Property, Hebron, KY  
Site/Area ID: TP-3

## SOILS

<b>Map Unit Name:</b> (Series and Phase): Jessup silt loam, 12 to 20 % slopes (JeD) (Taxonomy Subgroup): Typic Hapludalfs						Drainage Class: well drained Field Observations Confirm Mapped Type? Yes _____ No _____	
<b>Profile Description:</b>							
Depth (inches):	Horizon:	Matrix Color (Munsell Moist):	Mottle Colors (Munsell Moist):	Mottle (Abundance/Size):	Texture, Concretions, Structure:		
0-5	A	2.5Y 3/2	NA	NA	silty loam		
5-16	B	10YR 4/3	NA	NA	clay loam		
<b>Hydric Soil Indicators:</b>							
<input type="checkbox"/> Histosol			<input type="checkbox"/> Concretions				
<input type="checkbox"/> Histic Epipedon			<input type="checkbox"/> High Organic Content in Surface Layer in Sandy Soils				
<input type="checkbox"/> Sulfidic Odor			<input type="checkbox"/> Organic Streaking in Sandy Soil				
<input type="checkbox"/> Aquic Moisture Regimes			<input type="checkbox"/> Listed on Local Hydric Soils List				
<input type="checkbox"/> Reducing Conditions			<input type="checkbox"/> Listed on National Hydric Soils List				
<input type="checkbox"/> Gleyed or Low Chroma Colors			<input type="checkbox"/> Other (Explain in Remarks)				
<b>Remarks:</b>							

## WETLAND DETERMINATION

Hydrophytic Vegetation Present?	Yes _____	No <u>X</u>	Is this Sampling Point Within a Wetland? Yes _____ No <u>X</u>
Wetland Hydrology Present?	Yes <u>X</u>	No _____	
Hydric Soils Present?	Yes _____	No <u>X</u>	
<b>Remarks:</b>			



**DATA FORM**  
**ROUTINE WETLAND DETERMINATION**  
**(1987 COE Wetland Delineation Manual)**

<b>Project/Site:</b> 070-508 Litton Lane Property, Hebron, KY <b>Applicant/Owner:</b> Opus North Corporation <b>Investigator(s):</b> Matt Lauffer, Lindsey Hesch	<b>Date:</b> March 4, 2008 <b>County:</b> Boone <b>State:</b> KY
Do normal circumstances exist on the site? Yes <u>  X  </u> No <u>      </u> Is the site significantly disturbed (Atypical?) Yes <u>      </u> No <u>  X  </u> Is the area a potential problem area? Yes <u>      </u> No <u>  X  </u> (if needed, explain on reverse.)	<b>Community ID:</b> forest <b>Plot ID:</b> TP-4 Wetland 1 out point

**VEGETATION**

Dominant Plant Species:	Stratum:	Indicator:	Dominant Plant Species:	Stratum:	Indicator:
1. <i>Acer saccharum</i>	Tree	FACU-	10.		
2. <i>Fraxinus americana</i>	Tree	FACU	11.		
3. <i>Ulmus rubra</i>	Tree	FAC	12.		
4. <i>Lonicera maackii</i>	Shrub	UPL	13.		
5.			14.		
6.			15.		
7.			16.		
8.			17.		
9.			18.		

Percent of dominant species that are OBL, FACW or FAC (and excluding FAC-) = 25%

**Remarks:**

No herbaceous species present

**HYDROLOGY**

_____ Recorded Data (Describe in Remarks) _____ Stream, Lake, or Tide Gauge <u>  X  </u> _____ Aerial Photographs _____ No Recorded Data Available	<b>Wetland Hydrology Indicators:</b> <b>Primary Indicators:</b> _____ Inundated _____ Saturated in upper 12 inches _____ Water Marks _____ Drift Lines _____ Sediment Deposits _____ Drainage Patterns in Wetlands  <b>Secondary Indicators:</b> _____ Oxidized Root Channels in Upper 12 Inches _____ Water Stained Leaves _____ Local Soil Survey Data _____ FAC-Neutral Test _____ Others (Explain in Remarks)
<b>Field Observations:</b> Depth of Surface Water: <u>      0      </u> (inches) Depth to Free Water in Pit: <u>      &gt;16      </u> (inches) Depth to Saturated Soil: <u>      &gt;16      </u> (inches)	
<b>Remarks:</b>	

Project/Site: 070-508 / Opus Litton Lane Property, Hebron, KY  
Site/Area ID: TP-4

## SOILS

<b>Map Unit Name:</b> (Series and Phase): <u>Rossmoyne silt loam, 6 to 12% slopes (RsC)</u> Drainage Class: <u>moderately well drained</u> (Taxonomy Subgroup): <u>Aquic Fraguidalfs</u> Field Observations Confirm Mapped Type? Yes <u>X</u> No <u>      </u>					
<b>Profile Description:</b>					
Depth (inches):	Horizon:	Matrix Color (Munsell Moist):	Mottle Colors (Munsell Moist):	Mottle (Abundance/Size):	Texture, Concretions, Structure:
0-4	A	10YR 4/3	NA	NA	silty loam
4-16	B	10YR 5/4	10YR 5/6 and 10YR 6/1	medium, coarse	clay loam
<b>Hydric Soil Indicators:</b>					
<u>      </u> Histosol		<u>      </u> Concretions			
<u>      </u> Histic Epipedon		<u>      </u> High Organic Content in Surface Layer in Sandy Soils			
<u>      </u> Sulfidic Odor		<u>      </u> Organic Streaking in Sandy Soil			
<u>      </u> Aquic Moisture Regimes		<u>      </u> Listed on Local Hydric Soils List			
<u>      </u> Reducing Conditions		<u>      </u> Listed on National Hydric Soils List			
<u>      </u> Gleyed or Low Chroma Colors		<u>      </u> Other (Explain in Remarks)			
<b>Remarks:</b>					

## WETLAND DETERMINATION

Hydrophytic Vegetation Present?	Yes <u>      </u>	No <u>X</u>	Is this Sampling Point Within a Wetland? Yes <u>      </u> No <u>X</u>
Wetland Hydrology Present?	Yes <u>      </u>	No <u>X</u>	
Hydric Soils Present?	Yes <u>      </u>	No <u>X</u>	
<b>Remarks:</b>			

**DATA FORM**  
**ROUTINE WETLAND DETERMINATION**  
**(1987 COE Wetland Delineation Manual)**

<b>Project/Site:</b> 070-508 Litton Lane Property, Hebron, KY <b>Applicant/Owner:</b> Opus North Corporation <b>Investigator(s):</b> Matt Lauffer, Lindsey Hesch	<b>Date:</b> March 4, 2008 <b>County:</b> Boone <b>State:</b> KY
Do normal circumstances exist on the site? Yes <u>X</u> No _____ Is the site significantly disturbed (Atypical?) Yes _____ No <u>X</u> Is the area a potential problem area? Yes _____ No <u>X</u> (if needed, explain on reverse.)	<b>Community ID:</b> PFO <b>Plot ID:</b> TP-5 wetland 1 in

**VEGETATION**

Dominant Plant Species:	Stratum:	Indicator:	Dominant Plant Species:	Stratum:	Indicator:
1. <i>Planatus occidentalis</i>	Tree	FACW-	10.		
2. <i>Acer rubrum</i>	Tree	FAC	11.		
3. <i>Acer negundo</i>	Tree	FAC+	12.		
4.			13.		
5.			14.		
6.			15.		
7.			16.		
8.			17.		
9.			18.		

Percent of dominant species that are OBL, FACW or FAC (and excluding FAC-) = 100%

**Remarks:**

Non-dominants: *Rosa multiflora*, *Fraxinus pennsylvanica*, *Ulmus rubra*. No herbaceous species present

**HYDROLOGY**

_____ Recorded Data (Describe in Remarks) _____ Stream, Lake, or Tide Gauge <u>X</u> _____ Aerial Photographs _____ No Recorded Data Available	<b>Wetland Hydrology Indicators:</b> <b>Primary Indicators:</b> _____ Inundated <u>x</u> _____ Saturated in upper 12 inches _____ Water Marks _____ Drift Lines _____ Sediment Deposits <u>x</u> _____ Drainage Patterns in Wetlands  <b>Secondary Indicators:</b> _____ Oxidized Root Channels in Upper 12 Inches _____ Water Stained Leaves _____ Local Soil Survey Data <u>X</u> _____ FAC-Neutral Test _____ Others (Explain in Remarks)
<b>Field Observations:</b>  Depth of Surface Water: _____ 0 _____ (inches)  Depth to Free Water in Pit: _____ surface _____ (inches)  Depth to Saturated Soil: _____ surface _____ (inches)	
<b>Remarks:</b>  Floodplain of an ephemeral stream. This area of the stream has a bank depth of less than 6 inches. Non-wetland areas of the floodplain are adjacent to entrenched portions of the stream with bank depths ranging from 1 to 4 feet.	

Project/Site: 070-508 / Opus Litton Lane Property, Hebron, KY  
Site/Area ID: TP-5

## SOILS

<b>Map Unit Name:</b> (Series and Phase): Jessup silt loam, 12 to 20 % slopes (JeD) (Taxonomy Subgroup): Typic Hapludalfs						Drainage Class: well drained Field Observations Confirm Mapped Type? Yes _____ No _____	
<b>Profile Description:</b>							
Depth (inches):	Horizon:	Matrix Color (Munsell Moist):	Mottle Colors (Munsell Moist):	Mottle (Abundance/Size):	Texture, Concretions, Structure:		
0-16+	A	2.5Y 4/2	5YR 4/4	few / fine	silty clay		
<b>Hydric Soil Indicators:</b>							
<input type="checkbox"/> Histosol				<input type="checkbox"/> Concretions			
<input type="checkbox"/> Histic Epipedon				<input type="checkbox"/> High Organic Content in Surface Layer in Sandy Soils			
<input type="checkbox"/> Sulfidic Odor				<input type="checkbox"/> Organic Streaking in Sandy Soil			
<input type="checkbox"/> Aquic Moisture Regimes				<input type="checkbox"/> Listed on Local Hydric Soils List			
<input type="checkbox"/> Reducing Conditions				<input type="checkbox"/> Listed on National Hydric Soils List			
<input checked="" type="checkbox"/> Gleyed or Low Chroma Colors				<input type="checkbox"/> Other (Explain in Remarks)			
<b>Remarks:</b>  Chroma of two with mottles = hydric soil							

## WETLAND DETERMINATION

Hydrophytic Vegetation Present?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	Is this Sampling Point Within a Wetland? Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
Wetland Hydrology Present?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
Hydric Soils Present?	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>	
<b>Remarks:</b>  Wetland 1 point in			

**DATA FORM**  
**ROUTINE WETLAND DETERMINATION**  
**(1987 COE Wetland Delineation Manual)**

<b>Project/Site:</b> 070-508 Litton Lane Property, Hebron, KY <b>Applicant/Owner:</b> Opus North Corporation <b>Investigator(s):</b> Matt Lauffer, Lindsey Hesch	<b>Date:</b> March 4, 2008 <b>County:</b> Boone <b>State:</b> KY
Do normal circumstances exist on the site? Yes <u>X</u> No _____ Is the site significantly disturbed (Atypical?) Yes _____ No <u>X</u> Is the area a potential problem area? Yes _____ No <u>X</u> (if needed, explain on reverse.)	<b>Community ID:</b> forest floodplain <b>Plot ID:</b> TP-6

**VEGETATION**

Dominant Plant Species:	Stratum:	Indicator:	Dominant Plant Species:	Stratum:	Indicator:
1. <i>Acer rubrum</i>	Tree	FAC	10.		
2. <i>Fraxinus americana</i>	Tree	FACU	11.		
3. <i>Lonicera maackii</i>	Shrub	UPL	12.		
4.			13.		
5.			14.		
6.			15.		
7.			16.		
8.			17.		
9.			18.		

Percent of dominant species that are OBL, FACW or FAC (and excluding FAC-) = 33%

**Remarks:**

No herbaceous species present

**HYDROLOGY**

_____ Recorded Data (Describe in Remarks) _____ Stream, Lake, or Tide Gauge <u>X</u> _____ Aerial Photographs _____ No Recorded Data Available	<b>Wetland Hydrology Indicators:</b> <b>Primary Indicators:</b> _____ Inundated _____ Saturated in upper 12 inches _____ Water Marks _____ Drift Lines _____ Sediment Deposits _____ Drainage Patterns in Wetlands  <b>Secondary Indicators:</b> _____ Oxidized Root Channels in Upper 12 Inches _____ Water Stained Leaves _____ Local Soil Survey Data _____ FAC-Neutral Test _____ Others (Explain in Remarks)
<b>Field Observations:</b>  Depth of Surface Water: _____ 0 _____ (inches)  Depth to Free Water in Pit: _____ >16 _____ (inches)  Depth to Saturated Soil: _____ >16 _____ (inches)	
<b>Remarks:</b>	

Project/Site: 070-508 / Opus Litton Lane Property, Hebron, KY  
Site/Area ID: TP-6

## SOILS

<b>Map Unit Name:</b> (Series and Phase): Jessup silt loam, 12 to 20 % slopes (JeD) (Taxonomy Subgroup): Typic Hapludalfs						Drainage Class: well drained Field Observations Confirm Mapped Type? Yes _____ No _____	
<b>Profile Description:</b>							
Depth (inches):	Horizon:	Matrix Color (Munsell Moist):	Mottle Colors (Munsell Moist):	Mottle (Abundance/Size):	Texture, Concretions, Structure:		
0-16+	A	10YR 4/2	10YR 4/6	few, medium	silt loam		
<b>Hydric Soil Indicators:</b>							
_____ Histosol		_____ Concretions		_____ High Organic Content in Surface Layer in Sandy Soils			
_____ Histic Epipedon		_____ Organic Streaking in Sandy Soil		_____ Listed on Local Hydric Soils List			
_____ Sulfidic Odor		_____ Listed on National Hydric Soils List		_____ Other (Explain in Remarks)			
_____ Aquic Moisture Regimes		_____		_____			
_____ Reducing Conditions		_____		_____			
x _____ Gleyed or Low Chroma Colors		_____		_____			
<b>Remarks:</b>  Chroma 2 soil with mottles is hydric soil							

## WETLAND DETERMINATION

Hydrophytic Vegetation Present?	Yes _____	No <u>X</u>	Is this Sampling Point Within a Wetland? Yes _____ No <u>X</u>
Wetland Hydrology Present?	Yes _____	No <u>X</u>	
Hydric Soils Present?	Yes <u>X</u>	No _____	
<b>Remarks:</b>  			

**DATA FORM**  
**ROUTINE WETLAND DETERMINATION**  
**(1987 COE Wetland Delineation Manual)**

<b>Project/Site:</b> 070-508 Litton Lane Property, Hebron, KY <b>Applicant/Owner:</b> Opus North Corporation <b>Investigator(s):</b> Matt Lauffer, Lindsey Hesch	<b>Date:</b> March 4, 2008 <b>County:</b> Boone <b>State:</b> KY
Do normal circumstances exist on the site? Yes <u>  X  </u> No <u>      </u> Is the site significantly disturbed (Atypical?) Yes <u>      </u> No <u>  X  </u> Is the area a potential problem area? Yes <u>      </u> No <u>  X  </u> (if needed, explain on reverse.)	<b>Community ID:</b> Mesic forest <b>Plot ID:</b> TP-7

**VEGETATION**

Dominant Plant Species:	Stratum:	Indicator:	Dominant Plant Species:	Stratum:	Indicator:
1. <i>Lonicera maackii</i>	Shrub	UPL	10.		
2. <i>Fraxinus americana</i>	Tree	FACU	11.		
3. <i>Acer rubrum</i>	Tree	FAC	12.		
4. <i>Alliaria petiolata</i>	Herb	FACU-	13.		
5.			14.		
6.			15.		
7.			16.		
8.			17.		
9.			18.		

Percent of dominant species that are OBL, FACW or FAC (and excluding FAC-) = 25%

**Remarks:**

**HYDROLOGY**

_____ Recorded Data (Describe in Remarks) _____ Stream, Lake, or Tide Gauge <u>  X  </u> _____ Aerial Photographs _____ No Recorded Data Available	<b>Wetland Hydrology Indicators:</b> <b>Primary Indicators:</b> _____ Inundated _____ Saturated in upper 12 inches _____ Water Marks _____ Drift Lines _____ Sediment Deposits _____ Drainage Patterns in Wetlands  <b>Secondary Indicators:</b> _____ Oxidized Root Channels in Upper 12 Inches _____ Water Stained Leaves _____ Local Soil Survey Data _____ FAC-Neutral Test _____ Others (Explain in Remarks)
<b>Field Observations:</b>  Depth of Surface Water: <u>      0      </u> (inches)  Depth to Free Water in Pit: <u>      &gt;16      </u> (inches)  Depth to Saturated Soil: <u>      &gt;16      </u> (inches)	<b>Remarks:</b>

Project/Site: 070-508 / Opus Litton Lane Property, Hebron, KY  
Site/Area ID: TP-7

## SOILS

<b>Map Unit Name:</b> (Series and Phase): <u>Rossmoyne silt loam, 0 to 6% slopes (RsB)</u> (Taxonomy Subgroup): <u>Aquic Fraguidalfs</u>						<b>Drainage Class:</b> <u>moderately well drained</u> <b>Field Observations Confirm Mapped Type?</b> Yes <u>X</u> No <u>      </u>	
<b>Profile Description:</b>							
Depth (inches):	Horizon:	Matrix Color (Munsell Moist):	Mottle Colors (Munsell Moist):	Mottle (Abundance/Size):	Texture, Concretions, Structure:		
0-8	A	10YR 4/3	NA	NA	silt loam		
8-16	B	10YR 5/3	10YR 5/6	fine / many	silt loam		
<b>Hydric Soil Indicators:</b>							
<input type="checkbox"/> Histosol				<input type="checkbox"/> Concretions			
<input type="checkbox"/> Histic Epipedon				<input type="checkbox"/> High Organic Content in Surface Layer in Sandy Soils			
<input type="checkbox"/> Sulfidic Odor				<input type="checkbox"/> Organic Streaking in Sandy Soil			
<input type="checkbox"/> Aquic Moisture Regimes				<input type="checkbox"/> Listed on Local Hydric Soils List			
<input type="checkbox"/> Reducing Conditions				<input type="checkbox"/> Listed on National Hydric Soils List			
<input type="checkbox"/> Gleyed or Low Chroma Colors				<input type="checkbox"/> Other (Explain in Remarks)			
<b>Remarks:</b>							
Chroma of 3 with mottles = not hydric							

## WETLAND DETERMINATION

Hydrophytic Vegetation Present?	Yes <u>      </u>	No <u>X</u>	Is this Sampling Point Within a Wetland? Yes <u>      </u> No <u>X</u>
Wetland Hydrology Present?	Yes <u>      </u>	No <u>X</u>	
Hydric Soils Present?	Yes <u>      </u>	No <u>X</u>	
<b>Remarks:</b>			



**DATA FORM**  
**ROUTINE WETLAND DETERMINATION**  
**(1987 COE Wetland Delineation Manual)**

<b>Project/Site:</b> 070-508 Litton Lane Property, Hebron, KY <b>Applicant/Owner:</b> Opus North Corporation <b>Investigator(s):</b> Matt Lauffer, Lindsey Hesch	<b>Date:</b> March 4, 2008 <b>County:</b> Boone <b>State:</b> KY
Do normal circumstances exist on the site? Yes <u>X</u> No _____ Is the site significantly disturbed (Atypical?) Yes _____ No <u>X</u> Is the area a potential problem area? Yes _____ No <u>X</u> (if needed, explain on reverse.)	<b>Community ID:</b> PEM <b>Plot ID:</b> TP-8 Wetland 2 Point In

**VEGETATION**

Dominant Plant Species:	Stratum:	Indicator:	Dominant Plant Species:	Stratum:	Indicator:
1. <i>Leersia oryzoides</i>	Herb	OBL	10.		
2. <i>Eupatorium perfoliatum</i>	Herb	FACW+	11.		
3. <i>Lysimachia nummularia</i>	Herb	OBL	12.		
4. <i>Scirpus atrovirens</i>	Herb	OBL	13.		
5. <i>Rosa multiflora</i>	Shrub	FACU	14.		
6.			15.		
7.			16.		
8.			17.		
9.			18.		

Percent of dominant species that are OBL, FACW or FAC (and excluding FAC-) = 80%

**Remarks:**

**HYDROLOGY**

<div style="border-bottom: 1px solid black; margin-bottom: 5px;">           _____ Recorded Data (Describe in Remarks)         </div> <div style="border-bottom: 1px solid black; margin-bottom: 5px;">           _____ Stream, Lake, or Tide Gauge         </div> <div style="border-bottom: 1px solid black; margin-bottom: 5px;"> <u>X</u> Aerial Photographs         </div> <div style="border-bottom: 1px solid black; margin-bottom: 5px;">           _____ No Recorded Data Available         </div>	<b>Wetland Hydrology Indicators:</b> <b>Primary Indicators:</b> _____ Inundated <u>x</u> Saturated in upper 12 inches _____ Water Marks _____ Drift Lines _____ Sediment Deposits <u>x</u> Drainage Patterns in Wetlands  <b>Secondary Indicators:</b> _____ Oxidized Root Channels in Upper 12 Inches <u>x</u> Water Stained Leaves _____ Local Soil Survey Data _____ FAC-Neutral Test _____ Others (Explain in Remarks)
<b>Field Observations:</b>  Depth of Surface Water: _____ 0 _____ (inches)  Depth to Free Water in Pit: _____ 0 _____ (inches)  Depth to Saturated Soil: _____ 0 _____ (inches)	
<b>Remarks:</b>	

Project/Site: 070-508 / Opus Litton Lane Property, Hebron, KY  
Site/Area ID: TP-8

## SOILS

<b>Map Unit Name:</b> (Series and Phase): Jessup silt loam, 12 to 20 % slopes (JeD) (Taxonomy Subgroup): Typic Hapludalfs						Drainage Class: well drained Field Observations Confirm Mapped Type? Yes _____ No _____	
<b>Profile Description:</b>							
Depth (inches):	Horizon:	Matrix Color (Munsell Moist):	Mottle Colors (Munsell Moist):	Mottle (Abundance/Size):	Texture, Concretions, Structure:		
0-16	A	10YR 4/2	10YR 6/6	medium / many	silt loam		
<b>Hydric Soil Indicators:</b>							
_____ Histosol				_____ Concretions			
_____ Histic Epipedon				_____ High Organic Content in Surface Layer in Sandy Soils			
_____ Sulfidic Odor				_____ Organic Streaking in Sandy Soil			
_____ Aquic Moisture Regimes				_____ Listed on Local Hydric Soils List			
_____ Reducing Conditions				_____ Listed on National Hydric Soils List			
x _____ Gleyed or Low Chroma Colors				_____ Other (Explain in Remarks)			
<b>Remarks:</b>  Chroma 2 with mottles = hydric soil							

## WETLAND DETERMINATION

Hydrophytic Vegetation Present?	Yes	X	No	_____	Is this Sampling Point Within a Wetland? Yes X No _____
Wetland Hydrology Present?	Yes	X	No	_____	
Hydric Soils Present?	Yes	X	No	_____	
<b>Remarks:</b>  					

**DATA FORM**  
**ROUTINE WETLAND DETERMINATION**  
**(1987 COE Wetland Delineation Manual)**

<b>Project/Site:</b> 070-508 Litton Lane Property, Hebron, KY <b>Applicant/Owner:</b> Opus North Corporation <b>Investigator(s):</b> Matt Lauffer, Lindsey Hesch	<b>Date:</b> March 4, 2008 <b>County:</b> Boone <b>State:</b> KY
Do normal circumstances exist on the site? Yes <u>X</u> No _____ Is the site significantly disturbed (Atypical?) Yes _____ No <u>X</u> Is the area a potential problem area? Yes _____ No <u>X</u> (if needed, explain on reverse.)	<b>Community ID:</b> forest <b>Plot ID:</b> TP-9 Wetland 2 Point Out

**VEGETATION**

Dominant Plant Species:	Stratum:	Indicator:	Dominant Plant Species:	Stratum:	Indicator:
1. <i>Lonicera japonica</i>	Woody Vine	FAC-	10.		
2. <i>Rubus allegheniensis</i>	Shrub	FACU	11.		
3. <i>Celtis occidentalis</i>	Tree	FACU	12.		
4. <i>Acer saccharum</i>	Tree	FACU-	13.		
5. <i>Poa</i> sp.	Herb	NI	14.		
6.			15.		
7.			16.		
8.			17.		
9.			18.		

Percent of dominant species that are OBL, FACW or FAC (and excluding FAC-) = 0%

**Remarks:**

**HYDROLOGY**

_____ Recorded Data (Describe in Remarks) _____ Stream, Lake, or Tide Gauge <u>X</u> _____ Aerial Photographs _____ No Recorded Data Available	<b>Wetland Hydrology Indicators:</b> <b>Primary Indicators:</b> _____ Inundated _____ Saturated in upper 12 inches _____ Water Marks _____ Drift Lines _____ Sediment Deposits _____ Drainage Patterns in Wetlands  <b>Secondary Indicators:</b> _____ Oxidized Root Channels in Upper 12 Inches _____ Water Stained Leaves _____ Local Soil Survey Data _____ FAC-Neutral Test _____ Others (Explain in Remarks)
<b>Field Observations:</b>  Depth of Surface Water: _____ 0 _____ (inches)  Depth to Free Water in Pit: _____ >16 _____ (inches)  Depth to Saturated Soil: _____ >16 _____ (inches)	
<b>Remarks:</b>	

**Project/Site:** 070-508 / Opus Litton Lane Property, Hebron, KY  
**Site/Area ID:** TP-9

## SOILS

<b>Map Unit Name:</b>					
(Series and Phase): Jessup silt loam, 12 to 20% slopes			(Drainage Class): well drained		
(Taxonomy Subgroup) Aquic Fraguidalfs			Field Observations Confirm Mapped Type?		
			Yes <u>  X  </u> No <u>      </u>		
<b>Profile Description:</b>					
Depth (inches):	Horizon:	Matrix Color (Munsell Moist):	Mottle Colors (Munsell Moist):	Mottle (Abundance/Size):	Texture, Concretions, Structure:
0-3	A	10YR5/3	NA	NA	silty loam
3-16	B	10YR5/3	10YR5/6	medium/many	silty clay
<b>Hydric Soil Indicators:</b>					
<input type="checkbox"/> Histosol		<input type="checkbox"/> Concretions			
<input type="checkbox"/> Histic Epipedon		<input type="checkbox"/> High Organic Content in (Upper) Sandy Soils			
<input type="checkbox"/> Sulfidic Odor		<input type="checkbox"/> Organic Streaking in Sandy Soil			
<input type="checkbox"/> Aquic Moisture Regimes		<input type="checkbox"/> Listed on Local Hydric Soils List			
<input type="checkbox"/> Reducing Conditions		<input type="checkbox"/> Listed on National Hydric Soils List			
<input type="checkbox"/> Gleyed or Low Chroma Colors		<input type="checkbox"/> Other (Explain in Remarks)			
<b>Remarks:</b>					
Chroma 3 with mottles is not hydric					

## WETLAND DETERMINATION

Hydrophytic Vegetation Present?	Yes <u>      </u>	No <u>  X  </u>	Is this Sampling Point Within a Wetland? Yes <u>      </u> No <u>  X  </u>
Wetland Hydrology Present?	Yes <u>      </u>	No <u>  X  </u>	
Hydric Soils Present?	Yes <u>      </u>	No <u>  X  </u>	
<b>Remarks:</b>			

**DATA FORM**  
**ROUTINE WETLAND DETERMINATION**  
**(1987 COE Wetland Delineation Manual)**

<b>Project/Site:</b> 070-508 Litton Lane Property, Hebron, KY <b>Applicant/Owner:</b> Opus North Corporation <b>Investigator(s):</b> Matt Lauffer, Lindsey Hesch	<b>Date:</b> March 4, 2008 <b>County:</b> Boone <b>State:</b> KY
Do normal circumstances exist on the site? Yes <u>X</u> No _____ Is the site significantly disturbed (Atypical? Yes _____ No <u>X</u> Is the area a potential problem area? Yes _____ No <u>X</u> (if needed, explain on reverse.)	<b>Community ID:</b> forest <b>Plot ID:</b> TP-10

**VEGETATION**

Dominant Plant Species:	Stratum:	Indicator:	Dominant Plant Species:	Stratum:	Indicator:
1. <i>Fraxinus americana</i>	Tree	FACU	10.		
2.			11.		
3.			12.		
4.			13.		
5.			14.		
6.			15.		
7.			16.		
8.			17.		
9.			18.		
Percent of dominant species that are OBL, FACW or FAC (and excluding FAC-) = 0%					
<b>Remarks:</b>  Monoculture of <i>Fraxinus americana</i> . No herbaceous species present					

**HYDROLOGY**

_____ Recorded Data (Describe in Remarks) _____ Stream, Lake, or Tide Gauge <u>X</u> _____ Aerial Photographs _____ No Recorded Data Available	<b>Wetland Hydrology Indicators:</b> <b>Primary Indicators:</b> _____ Inundated _____ Saturated in upper 12 inches _____ Water Marks _____ Drift Lines _____ Sediment Deposits _____ Drainage Patterns in Wetlands  <b>Secondary Indicators:</b> _____ Oxidized Root Channels in Upper 12 Inches _____ Water Stained Leaves _____ Local Soil Survey Data _____ FAC-Neutral Test _____ Others (Explain in Remarks)
<b>Field Observations:</b>  Depth of Surface Water: _____ 0 _____ (inches)  Depth to Free Water in Pit: _____ >16 _____ (inches)  Depth to Saturated Soil: _____ >16 _____ (inches)	
<b>Remarks:</b>	

**Project/Site:** 070-508 / Opus Litton Lane Property, Hebron, KY  
**Site/Area ID:** TP-10

## SOILS

**Map Unit Name:**  
 (Series and Phase): Rossmoyne silt loam, 6 to 12% slopes (Drainage Class: moderately well drained)  
 (Taxonomy Subgroup) Aquic Fraguidalfs Field Observations Confirm Mapped Type?  
 Yes X No       

### Profile Description:

Depth (inches):	Horizon:	Matrix Color (Munsell Moist):	Mottle Colors (Munsell Moist):	Mottle (Abundance/Size):	Texture, Concretions, Structure:
0-16	A	2.5Y 5/3	10YR 6/6	many / medium	clay loam

### Hydric Soil Indicators:

<input type="checkbox"/> Histosol	<input type="checkbox"/> Concretions
<input type="checkbox"/> Histic Epipedon	<input type="checkbox"/> High Organic Content in (Upper) Sandy Soils
<input type="checkbox"/> Sulfidic Odor	<input type="checkbox"/> Organic Streaking in Sandy Soil
<input type="checkbox"/> Aquic Moisture Regimes	<input type="checkbox"/> Listed on Local Hydric Soils List
<input type="checkbox"/> Reducing Conditions	<input type="checkbox"/> Listed on National Hydric Soils List
<input type="checkbox"/> Gleyed or Low Chroma Colors	<input type="checkbox"/> Other (Explain in Remarks)

### Remarks:

**Chroma 3 with mottles is not hydric**

## WETLAND DETERMINATION

Hydrophytic Vegetation Present?	Yes <u>X</u>	No <u>      </u>	Is this Sampling Point Within a Yes <u>      </u> No <u>X</u>
Wetland Hydrology Present?	Yes <u>      </u>	No <u>X</u>	
Hydric Soils Present?	Yes <u>      </u>	No <u>X</u>	

### Remarks:

---

## **APPENDIX II**

### **SITE PHOTOGRAPHS**

---



Photo #1: View of Wetland 1 on the floodplain of Stream 3. Photo taken facing east.



Photo #2: View of Wetland 1 on the floodplain of Stream 3. Photo taken facing north.





Photo #3: View of Wetland 2 and adjacent pond. Photo taken facing southwest.



Photo #4: View of Wetland 2. The Interstate 275 embankment can be seen in the background. Photo taken facing northeast.



Photo #5: View of the pond in the northwest portion of the Property. Photo taken facing southeast.



Photo #6: View of a portion of the pond in the northwest portion of the property. Photo taken facing south.



Photo #7: View of Stream 1 facing downstream. Photo taken facing north.



Photo #8: View of Stream 1 facing upstream. Photo taken facing south.



Photo #9: View of Stream 2 at the confluence with of Stream 1. Photo taken facing northwest.



Photo #10: View of the headwaters of Stream 2. Photo taken facing northwest.



Photo #11: View of Stream 2B facing upstream. Photo taken facing southeast.



Photo #12: View of the ephemeral portion of Stream 3 facing upstream. Photo taken facing east.



Photo #13: View of intermittent portion of Stream 3, downstream of Wetland 1, facing downstream. Photo taken facing west.



Photo #14: View of Stream 3 at the confluence with Stream 4. Photo taken facing southeast.



Photo #15: View of Stream 3 exiting the Property. Photo taken facing northwest.



Photo #16: View of Stream 4 facing upstream. Photo taken facing south.



Photo #17: View of the ephemeral portion of Stream 5 facing upstream. Photo taken facing northeast.



Photo #18: View of the intermittent portion of Stream 5 facing upstream. Photo taken facing east.





Photo #19: View of Stream 6. Photo taken facing northeast.



Photo #20: View of Stream 6. Photo taken facing southwest.



Photo #21: View of Stream 7. Photo taken facing northeast.



Photo #22: View of Stream 7. Photo taken facing southwest.



Photo #23: View of the headwaters of Stream 7. The Interstate 275 embankment can be seen in the background. Photo taken facing northeast.



Photo #24: View of Stream 8. Photo taken facing southwest.



Photo #25: View of *Rubus allegheniensis* and *Lonicera maackii* with a *Robinia pseudoacacia* overstory near Wetland Determination Test Pit #1. Photo taken facing west.



Photo #26: View of old field habitat at Wetland Determination Test Pit #2. Photo taken facing east.



Photo #27: View of the forested floodplain at Wetland Determination Test Pit #3. Photo taken facing northwest.



Photo #28: View of the forest at Wetland Determination Test Pit #4. Photo taken facing north.



Photo #29: View of the forested floodplain at Wetland Determination Test Pit #6. Photo taken facing west.



Photo #30: View of forest with a *Lonicera maackii* understory at Wetland Determination Test Pit #7. Photo taken facing east.



Photo #31: View of the forest at Wetland Determination Test Pit #10. Photo taken facing east.




Photo #32: View of old field habitat in the southern portion of the Property. Photo taken facing north.



Photo #33: View of old field habitat in the southern portion of the Property.  
Photo taken facing northeast.



Photo #34: View of old field habitat in the southern end of the Property. Photo  
taken facing south.





Photo #35: View of old field habitat southeast of the pond. Photo taken facing southwest.



Photo #36: View of old field habitat located between Stream 3 and the pond. Photo taken facing south.



Photo #37: View of early successional forest located between Stream 3 and the pond. Photo taken facing west.



Photo #38: View of early successional forest located near Stream 6. Photo taken facing south.



Photo #39: View of forest with an understory of *Lonicera maackii* located east of Stream 7. Photo taken facing east.



Photo #40: View of Stream 9 in the eastern portion of the Property. Photo taken facing north.

---

**ATTACHMENT C**

**AGENCY CLEARANCE DOCUMENTATION**

---



## United States Department of the Interior

RECEIVED

FEB 05 2009

FISH AND WILDLIFE SERVICE  
Kentucky Ecological Services Field Office  
330 West Broadway, Suite 265  
Frankfort, Kentucky 40601  
(502) 695-0468

February 3, 2009

Mr. Daniel Godee  
Civil & Environmental Consultants  
4274 Glendale Milford Road  
Cincinnati, OH 45242

Subject: FWS #2008-B-0477; Hebron Industrial Development Site, Indiana Bat Hibernacula and Running Buffalo Clover Survey Results; Boone County, Kentucky.

Dear Mr. Goode:

Thank you for your correspondence dated January 14, 2009 providing the results of the running buffalo clover (*Trifolium stoloniferum*) survey and additional information regarding potential Indiana bat (*Myotis sodalis*) habitat on the proposed project site. This information was provided in response to our comments dated May 5, 2008. Fish and Wildlife personnel have reviewed the submitted information and offer the following comments:

### Indiana bat

The proposed project will not impact any known or potential hibernacula and any removal of trees will only occur between October 15 and March 31. As such, the Service concurs that the proposed project is not likely to adversely affect the federally endangered Indiana bat.

### Running Buffalo Clover


A survey for running buffalo clover was conducted on June 25 and 26, 2008 using transects spaced 15 to 25 feet apart. All species of clover and those with clover-like leaves were closely inspected when encountered. The Service has reviewed the submitted survey report and finds the report acceptable. Based on the negative survey results, the Service concurs that the proposed project is not likely to adversely affect the federally endangered running buffalo clover.

In view of this information and our concurrence with the determinations, we believe that the requirements of section 7 have been fulfilled. Please note that obligations under Section 7 of the Act must be reconsidered if (1) new information reveals impacts of the proposed action that may affect listed species or critical habitat in a manner not previously considered, (2) the proposed action is subsequently modified to include activities which were not considered during this

consultation, or (3) new species are listed or critical habitat designated that might be affected by the proposed action.

We appreciate the opportunity to review the subject report. Please contact Jennifer Garland at 502-695-0468 (ext. 115) if you have questions regarding these comments.

Sincerely,

A handwritten signature in black ink, appearing to read "Virgil Lee Andrews, Jr.", with a large, stylized flourish extending from the end of the signature.


Virgil Lee Andrews, Jr.  
Field Supervisor

---

**ATTACHMENT D**

**PRELIMINARY GRADING PLAN**

---



INDUSTRIAL BLDG.  
506,000 S.F.  
F.F. = 98.71.00

# PRELIMINARY GRADING PLAN OPUS NORTH CORPORATION

SCALE: 1"=40'  
DATE: 2-27-08  
DRAWN: SJD  
CHECKED:  
APP: JCN  
JOB NO.: 070808-001  
CITY: BIRMINGHAM, AL

NO.	REVISIONS
1	
2	
3	
4	
5	
6	
7	
8	
9	
10	

